STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS AND MINING							FORI		
APPLI	CATION FOR	PERMIT TO DRILI	L			1. WELL NAME and NUMBER NBU 922-32F3T			
2. TYPE OF WORK DRILL NEW WELL REENTER P&A WELL DEEPEN WELL					3. FIELD OR WILDO	CAT NATURAL BUTTES			
4. TYPE OF WELL Gas We	ell Coalb	ed Methane Well: NO				5. UNIT or COMMUI	NITIZATION AGREI NATURAL BUTTES	EMENT NAME	
5. NAME OF OPERATOR KERR	-MCGEE OIL & G	AS ONSHORE, L.P.				7. OPERATOR PHON	NE 720 929-6587		
B. ADDRESS OF OPERATOR P.O	. Box 173779, D	enver, CO, 80217				9. OPERATOR E-MA mary.m	IL ondragon@anadarko	.com	
10. MINERAL LEASE NUMBER (FEDERAL, INDIAN, OR STATE)		11. MINERAL OWNER FEDERAL INC	RSHIP DIAN (FEE (12. SURFACE OWNI	ERSHIP DIAN (STATE (FEE (III)	
ML 22649 13. NAME OF SURFACE OWNER (if box 12	= 'fee')	TEDERALITINE	ZIAN [Z SIAIL (S, 122(0)	14. SURFACE OWN		~ ~	
15. ADDRESS OF SURFACE OWNER (if box	12 = 'fee')					16. SURFACE OWNI	ER E-MAIL (if box 1	.2 = 'fee')	
17. INDIAN ALLOTTEE OR TRIBE NAME (if box 12 = 'INDIAN')		18. INTEND TO COM		LE PRODUCT		19. SLANT			
		YES (Submit C	Commin	gling Applicat	ion) NO 📵	VERTICAL DIR	RECTIONAL (HO	ORIZONTAL (
20. LOCATION OF WELL	FO	OTAGES	Q	TR-QTR	SECTION	TOWNSHIP	RANGE	MERIDIAN	
LOCATION AT SURFACE	CATION AT SURFACE 2111 FN			SENW	32	9.0 S	22.0 E	S	
Top of Uppermost Producing Zone	2111 FN	NL 1824 FWL S		SENW	32	9.0 S	22.0 E	S	
At Total Depth	2111 FN	NL 1824 FWL SENW		32	9.0 S	22.0 E	S		
21. COUNTY UINTAH		22. DISTANCE TO NEAREST LEASE LINE (Feet) 1824 23. NUMBER OF ACRES IN DRILLING UNIT				JNIT			
			25. DISTANCE TO NEAREST WELL IN SAME POOL Applied For Drilling or Completed) 606 26. PROPOSED DEPTH MD: 9200 TVD: 9200						
27. ELEVATION - GROUND LEVEL 5003		28. BOND NUMBER 22013542			29. SOURCE OF DRILLING WATER / WATER RIGHTS APPROVAL NUMBER IF APPLICABLE Permit #43-8496				
		A	TTACH	HMENTS					
VERIFY THE FOLLOWING	ARE ATTACH	ED IN ACCORCAN	CE WI	TH THE UT	TAH OIL AND G	AS CONSERVATION	ON GENERAL RU	LES	
▼ WELL PLAT OR MAP PREPARED BY	LICENSED SUR	VEYOR OR ENGINEE	R	COMPLETE DRILLING PLAN					
AFFIDAVIT OF STATUS OF SURFACE	OWNER AGRE	EMENT (IF FEE SURF	ACE)	CE) FORM 5. IF OPERATOR IS OTHER THAN THE LEASE OWNER					
DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY DRILLED)				TOPOGRAPHICAL MAP					
NAME Kathy Schneebeck-Dulnoan	y Schneebeck-Dulnoan TITLE Staff Regulatory Analyst			PHONE 720 929-6007					
SIGNATURE DATE 04/30/2009				EMAIL Kathy.So	chneebeckDulnoan@ar	nadarko.com			
API NUMBER ASSIGNED 43047503490000	APPR	COVAL			Boll	Rejill			
					Permi	t Manager			


API Well No: 43047503490000 Received: 4/13/2009

	Proposed Hole, Casing, and Cement						
String	Hole Size	Casing Size	Top (MD)	Bottom (MD)			
Prod	7.875	4.5	0	9289			
Pipe	Grade	Length	Weight				
	Grade I-80 LT&C	9200	11.6		П		

API Well No: 43047503490000 Received: 4/13/2009

	Proposed Hole, Casing, and Cement					
String	Hole Size	Casing Size	Top (MD)	Bottom (MD)		
Surf	12.25	9.625	0	2300		
Pipe	Grade	Length	Weight			
	Grade J-55 LT&C	2300	36.0			

T9S, R22E, S.L.B.&M.



LEGEND:

= 90° SYMBOL

PROPOSED WELL HEAD.

= SECTION CORNERS LOCATED.

(NAD 83)

LATITUDE = $39^{\circ}59'38.36''$ (39.993989) LONGITUDE = $109^{\circ}28'00.39"$ (109.466775)

(NAD 27)

LATITUDE = $39^{\circ}59'38.48''$ (39.994022)


LONGITUDE = $109^{27}57.92^{20}$ (109.466089)

Kerr-McGee Oil & Gas Onshore LP

Well location, NBU #922-32F3T, located as shown in the SE 1/4 NW 1/4 of Section 32, T9S, R22E, S.L.B.&M., Uintah County, Utah.

BASIS OF ELEVATION

TWO WATER TRIANGULATION STATION LOCATED IN THE NW 1/4 OF SECTION 1, T10S, R21E, S.L.B.&M. TAKEN FROM THE BIG PACK MTN NE QUADRANGLE, UTAH. UINTAH COUNTY, 7.5 MINUTE SERIES (TOPOGRAPHICAL MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 5238 FEET.



CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAN WAS PREPARED FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO BEST OF MY KNOWLEDGE AND BELIEF

> REGISTRATION NO. 161319 STATE OF OTAHITE

Kerr-McGee Oil & Gas Onshore LP

REVISED: 02-26-09 C.C. REVISED: 09-24-08

UINTAH ENGINEERING LAND SURVEYING 85 SOUTH 200 EAST VERNAL. UTAH 84078 (435) 789-1017

SCALE 1" = 1	000'		DATE SURVEYED: DATE DRAWN: 05-27-08 06-06-08
PARTY			REFERENCES
L.K.	D.D.	S.L.	G.L.O. PLAT
WEATHER		FILE	•
COLD Kerr			Kerr-McGee Oil & Gas Onshore IP

NBU 922-32F3T

Pad: NBU 922-32F (CIGE 106D) Surface: 2,111' FNL, 1,824' FWL (SE/4NW/4) Sec. 32 T9S R22E

> Uintah, Utah Mineral Lease: ML 22649

ONSHORE ORDER NO. 1

DRILLING PROGRAM

1. – 2. <u>Estimated Tops of Important Geologic Markers</u>: <u>Estimated Depths of Anticipated Water, Oil, Gas, or Mineral Formations</u>:

<u>Formation</u>	<u>Depth</u>	Resource
Uinta	0 – Surface	
Green River	1,294'	
Birds Nest	1,621'	Water
Mahogany	2,093'	Water
Wasatch	4,519'	Gas
Mesaverde	7,072'	Gas
MVU2	7,992'	Gas
MVL1	8,588'	Gas
TD	9,200'	

3. Pressure Control Equipment (Schematic Attached)

Please refer to the attached Drilling Program.

4. Proposed Casing & Cementing Program:

Please refer to the attached Drilling Program.

5. <u>Drilling Fluids Program:</u>

Please refer to the attached Drilling Program.

Evaluation Program:

Please refer to the attached Drilling Program.

7. **Abnormal Conditions:**

Maximum anticipated bottomhole pressure calculated at 9,200' TD, approximately equals 5,875 psi (calculated at 0.64 psi/foot).

Maximum anticipated surface pressure equals approximately 3,851 psi (bottomhole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot).

8. Anticipated Starting Dates:

Drilling is planned to commence immediately upon approval of this application.

9. Variances:

Please refer to the attached Drilling Program.

Onshore Order #2 – Air Drilling Variance

Kerr-McGee Oil & Gas Onshore LP (KMG) respectfully requests a variance to several requirements associated with air drilling outlined in Onshore Order 2

- Blowout Prevention Equipment (BOPE) requirements;
- Mud program requirements; and
- Special drilling operation (surface equipment placement) requirements associated with air drilling.

This Standard Operating Practices addendum provides supporting information as to why KMG current air drilling practices for constructing the surface casing hole should be granted a variance to Onshore Order 2 air drilling requirements.

The reader should note that the air rig is used only to construct a stable surface casing hole through a historically difficult lost circulation zone. A conventional rotary rig follows the air rig, and is used to drill and construct the majority of the wellbore.

More notable, KMG has used the air rig layout and procedures outlined below to drill the surface casing hole in approximately 675 wells without incident of blow out or loss of life.

Background

In a typical well, KMG utilizes an air rig for drilling the surface casing hole, an interval from the surface to surface casing depths, which varies in depth from 1,700 to 2,800 feet. The air rig drilling operation does not drill through productive or over pressured formations in KMG field, but does penetrate the Uinta and Green River Formations. The purpose of the air drilling operation is to overcome the severe loss circulation zone in the Green River known as the Bird's Nest while creating a stable hole for the surface casing. The surface casing hole is generally drilled to approximately 500 feet below the Bird's Nest.

Before the surface air rig is mobilized, a rathole rig is utilized to set and cement conductor pipe through a competent surface formation. Generally, the conductor is set at 40 feet. In some cases, conductor may be set deeper in areas that the surface formation is not found competent. This rig also drills the rat and mouse holes in preparation for the surface casing and production string drilling operations.

The air rig is then mobilized to drill the surface casing hole by drilling a 12-1/4 inch hole to just above the Bird's Nest interval with an air hammer. The hammer is then tripped and replaced with a 12-1/4 inch tri-cone bit. The tri-cone bit is used to drill to the surface casing point, approximately 500 feet below the loss circulation zone (Bird's Nest). The 9-5/8 inch surface casing is then run and cemented in place, thereby isolating the lost circulation zone.

KMG fully appreciates Onshore Order 2 well control and safety requirements associated with a typical air drilling operations. However, the requirements of Onshore Order 2 are excessive with respect to the air rig layout and drilling operation procedures that are currently in practice to drill and control the surface casing hole in KMG Fields.

Variance for BOPE Requirements

The air rig operation utilizes a properly lubricated and maintained air bowl diverter system which diverts the drilling returns to a six-inch blooie line. The air bowl is the only piece of BOPE equipment which is installed during drilling operations and is sufficient to contain the air returns associated with this drilling operation. As was discussed earlier, the drilling of the surface hole does not encounter any over pressured or productive zones, and as a result standard BOPE equipment should not be required. In addition, standard drilling practices do not support the use of BOPE on 40 feet of conductor pipe.

Variance for Mud Material Requirements

Onshore Order 2 also states that sufficient quantities of mud materials shall be maintained or readily accessible for the purpose of assuring adequate well control. Once again, the surface hole drilling operations does not encounter over pressured or productive intervals, and as a result there is not a need to control pressure in the surface hole with a mud system. Instead of mud, the air rigs utilize water from the reserve pit for well control, if necessary. A skid pump which is located near the reserve pit (see attachment) will supply the water to the well bore.

Variance for Special Drilling Operation (surface equipment placement) Requirements

Onshore Order 2 requires specific safety distances or setbacks for the placement of associated standard air drilling equipment, wellbore, and reserve pits. The air rigs used to drill the surface holes are not typical of an air rig used to drill a producing hole in other parts of the US. These are smaller in nature and designed to fit a KMG location. The typical air rig layout for drilling surface hole in the field is attached.

Typically the blooie line discharge point is required to be 100 feet from the well bore. In the case of a KMG well, the reserve pit is only 45 feet from the rig and is used for the drill cuttings. The blooie line, which transports the drill cuttings from the well to the reserve pit, subsequently discharges only 45 feet from the well bore.

Typically the air rig compressors are required to be located in the opposite direction from the blooie line and a minimum of 100 feet from the well bore. At the KMG locations, the air rig compressors are approximately 40 feet from the well bore and approximately 60 feet from the blooie line discharge due to the unique air rig design. The air compressors (see attachment) are located on the rig (1250 cfm) and on a standby trailer (1170 cfm). A booster sits between the two compressors and boosts the output from 350 psi to 2000 psi. The design does put the booster and standby compressor opposite from the blooie line.

Lastly, Onshore Order 2 addresses the need for an automatic igniter or continuous pilot light on the blooie line. The air rig does not utilize an igniter as the surface hole drilling operation does not encounter productive formations.

Conclusion


The air rig operating procedures and the attached air rig layout have effectively maintained well control while drilling the surface holes in KMG Fields. KMG respectfully requests a variance from Onshore Order 2 with respect to air drilling well control requirements as discussed above.


10. Other Information:

Please refer to the attached Drilling Program.



KERR-McGEE OIL & GAS ONSHORE LP DRILLING PROGRAM







KERR-McGEE OIL & GAS ONSHORE LP

DRILLING PROGRAM

CASING PROGRAM

								[DESIGN FACT	ORS
	SIZE	INT	ERVA	L	WT.	GR.	CPLG.	BURST	COLLAPSE	TENSION
CONDUCTOR	14"	(0-40'							
								3,520	2,020	453,000
SURFACE	9-5/8"	0	to	2300	36.00	J-55	LTC	0.89	1.88	6.96
								7,780	6,350	201,000
PRODUCTION	4-1/2"	0	to	9200	11.60	I-80	LTC	1.97	1.06	2.16

- 1) Max Anticipated Surf. Press.(MASP) (Surface Casing) = (Pore Pressure at next csg point-(0.22 psi/ft-partial evac gradient x TVD of next csg point))
- 2) MASP (Prod Casing) = Pore Pressure at TD (0.22 psi/ft-partial evac gradient x TD)

(Burst Assumptions: TD = 12.5 ppg) 0.22 psi/ft = gradient for partially evac wellbore (Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing*Buoy.Fact. of water)

MASP 3,851 psi

3) Maximum Anticipated Bottom Hole Pressure (MABHP) = Pore Pressure at TD

(Burst Assumptions: TD = 12.5 ppg) 0.64 psi/ft = bottomhole gradient

(Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing*Buoy.Fact. of water)

MABHP 5,875 psi

CEMENT PROGRAM

	FT. OF FILL	DESCRIPTION	SACKS	EXCESS	WEIGHT	YIELD
SURFACE LEAD	500	Premium cmt + 2% CaCl	215	60%	15.60	1.18
Option 1		+ .25 pps flocele				
TOP OUT CMT (1)	200	20 gals sodium silicate + Premium cmt	50		15.60	1.18
		+ 2% CaCl + .25 pps flocele				
TOP OUT CMT (2)	as required	Premium cmt + 2% CaCl	as req.		15.60	1.18
SURFACE		NOTE: If well will circulate water to su	ırface, opt	ion 2 will be	utilized	
Option 2 LEAD	1500	Prem cmt + 16% Gel + 10 pps gilsonite	170	35%	11.00	3.82
		+.25 pps Flocele + 3% salt BWOC				
TAIL	500	Premium cmt + 2% CaCl 180 35°		35%	15.60	1.18
		+ .25 pps flocele				
TOP OUT CMT	as required	Premium cmt + 2% CaCl	as req.		15.60	1.18
PROPLICATION	4.040	Descrives Lite II + 20/ KOL + 0.05 and	440	000/	44.00	0.00
PRODUCTION LEAD	4,010'	Premium Lite II + 3% KCI + 0.25 pps	440	60%	11.00	3.38
		celloflake + 5 pps gilsonite + 10% gel				
		+ 0.5% extender				
TAIL	5,190'	50/50 Poz/G + 10% salt + 2% gel	1450	60%	14.30	1.31
		+.1% R-3				

^{*}Substitute caliper hole volume plus 0% excess for LEAD if accurate caliper is obtained

FLOAT EQUIPMENT & CENTRALIZERS

SURFACE

Guide shoe, 1 jt, insert float. Centralize first 3 joints with bow spring centralizers. Thread lock guide shoe.

PRODUCTION

Float shoe, 1 jt, float collar. Centralize first 3 joints & every third joint to top of tail cement with bow spring centralizers.

ADDITIONAL INFORMATION

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.

BOPE: 11" 5M with one annular and 2 rams. The BOPE will be installed before the production hole is drilled and tested to 5,000 psi (annular to 2,500 psi) prior to drilling out the surface casing shoe. Record on chart recorder and tour sheet. Function test rams on each trip.


Maintain safety valve and inside BOP on rig floor at all times. Most rigs have top drives; however, if used, the Kelly is to be equipped with upper and lower kelly valves.

Drop Totco surveys every 2000'. Maximum allowable hole angle is 5 degrees.
Most rigs have PVT Systems for mud monitoring. If no PVT is available, visual monitoring will be utililzed.


	Most rigs have PVT Systems for mud monitoring. If no PVT is available, visual monitoring will be utililzed.			
DRILLING	ENGINEER:		DATE:	
		John Huycke / Grant Schluender		
DRILLING	SUPERINTENDENT:		DATE:	
		John Merkel / Lovel Young		


^{*}Substitute caliper hole volume plus 10% excess for TAIL if accurate caliper is obtained


EXHIBIT A NBU 922-32F3T




SCHEMATIC DIAGRAM OF 5,000 PSI BOP STACK









Kerr-McGee Oil & Gas Onshore LP NBU #922-32E2S, #922-32K1S, #922-32F3T & #922-32F2S SECTION 32, T9S, R22E, S.L.B.&M.

PROCEED IN A WESTERLY DIRECTION FROM VERNAL, UTAH ALONG U.S. HIGHWAY 40 APPROXIMATELY 14.0 MILES TO THE JUNCTION OF STATE HIGHWAY 88: EXIT LEFT AND PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 17.0 MILES TO OURAY, UTAH; PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 6.9 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTHEAST: TURN LEFT AND PROCEED IN A SOUTHEASTERLY, THEN EASTERLY DIRECTION APPROXIMATELY 5.0 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE NORTHWEST: TURN LEFT AND PROCEED IN A NORTHWESTERLY DIRECTION APPROXIMATELY 0.3 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE NORTHEAST; TURN RIGHT AND PROCEED IN A NORTHEASTERLY DIRECTION APPROXIMATELY 3.8 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE NORTHEAST: PROCEED IN A NORTHEASTERLY DIRECTION APPROXIMATELY 0.9 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTHWEST; TURN RIGHT AND PROCEED IN A SOUTHWESTERLY, THEN SOUTHEASTERLY DIRECTION APPROXIMATELY 4.0 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTHEAST; TURN LEFT AND PROCEED IN A SOUTHEASTERLY, THEN EASTERLY, THEN NORTHERLY DIRECTION APPROXIMATELY 2.3 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE EAST; TURN RIGHT AND PROCEED IN AN EASTERLY DIRECTION APPROXIMATELY 0.15 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTHWEST; TURN RIGHT AND PROCEED IN A SOUTHWESTERLY DIRECTION APPROXIMATELY 0.15 MILES TO THE PROPOSED LOCATION.

TOTAL DISTANCE FROM VERNAL, UTAH TO THE PROPOSED WELL LOCATION IS APPROXIMATELY 54.5 MILES.

Kerr-McGee Oil & Gas Onshore LP

NBU #922-32E2S, #922-32K1S, #922-32F3T & #922-32F2S

LOCATED IN UINTAH COUNTY, UTAH SECTION 32, T9S, R22E, S.L.B.&M.



PHOTO: VIEW FROM CORNER 5 TO LOCATION STAKES

CAMERA ANGLE: NORTHWESTERLY



PHOTO: VIEW OF EXISTINGACCESS

CAMERA ANGLE: SOUTHWESTERLY





NBU 922-32F3T

Pad: NBU 922-32F (CIGE 106D) Surface: 2,111' FNL, 1,824' FWL (SE/4NW/4) Sec. 32 T9S R22E

> Uintah, Utah Mineral Lease: ML 22649

ONSHORE ORDER NO. 1

MULTI-POINT SURFACE USE & OPERATIONS PLAN

1. <u>Existing Roads</u>:

Refer to Topo Map A for directions to the location.

Refer to Topo Maps A and B for location of access roads within a 2-mile radius.

Refer to Topo Maps A and B for location of access roads within a 2-mile radius.

All existing roads will be maintained and kept in good repair during all drilling and completion operations associated with this well.

2. Planned Access Roads:

Approximately ± 0.0 mi. (± 0 ') of new access road is proposed. Please refer to the attached Topo Map B.

The upgraded and new portions of the access road will be crowned and ditched with a running surface of 18 feet and a maximum disturbed width of 30 feet. Appropriate water control will be installed to control erosion.

Existence of pipelines; maximum grade; turnouts; major cut and fills, culverts, or bridges; gates, cattle guards, fence cuts, or modifications to existing facilities were determined at the on-site.

The access road was centerline flagged during time of staking.

Surfacing material may be necessary, depending upon weather conditions.

Surface disturbance and vehicular traffic will be limited to the approved location and approved access route. Any additional area needed will be approved in advance.

3. Location of Existing Wells Within a 1-Mile Radius:

Please refer to Topo Map C.

4. <u>Location of Existing & Proposed Facilities:</u>

The following guidelines will apply if the well is productive.

All production facilities will be located on the disturbed portion of the well pad and at a minimum of 25 feet from the toe of the back slope or the top of the fill slope.

A dike will be constructed completely around those production facilities which contain fluids (i.e., production tanks, produced water tanks, and/or heater/treater). These dikes will be constructed of compacted subsoil, be impervious, hold 100% of the capacity of the largest tank, and be independent of the back cut.

All permanent (on-site six months or longer) above the ground structures constructed or installed, including pumping units, will be painted a flat, non-reflective, earthtone color to match one of the standard environmental colors, as determined by the five state Rocky Mountain Inter-Agency Committee.

All facilities will be painted within six months of installation. Facilities required to comply with the Occupational Safety and Health Act (OSHA) will be excluded. The required color is Shadow Gray, a non-reflective earthtone.

Any necessary pits will be properly fenced to protect livestock and prevent wildlife entry.

5. Location and Type of Water Supply:

Water for drilling purposes will be obtained from Dalbo Inc.'s underground well located in Ouray, Utah, Sec. 32 T4S R3E, Water User Claim #43-8496, Application #53617.

Water will be hauled to location over the roads marked on Maps A and B.

No water well is to be drilled on this lease.

6. Source of Construction Materials:

Surface and subsoil materials in the immediate area will be utilized.

Any gravel will be obtained from a commercial source.

7. Methods of Handling Waste Materials:

Drill cuttings will be contained and buried in the reserve pit.

Drilling fluids, including salts and chemicals, will be contained in the reserve pit. Upon termination of drilling and completion operations, the liquid contents of the reserve pit will be removed and disposed of at an approved waste disposal facility within 120 days after drilling is terminated.

The reserve pit will be constructed on the location and will not be located within natural drainage, where a flood hazard exists or surface runoff will destroy or damage the pit walls. The reserve pit will be constructed so that it will not leak, break, or allow discharge of liquids.

A plastic reinforced liner and felt will be used; it will be a minimum of 20 mil thick, with sufficient bedding used to cover any rocks. The liner will overlap the pit walls and be covered with dirt and/or rocks to hold it in place. No trash or scrap that could puncture the liner will be disposed of in the pit. Any spills of oil, gas, salt water, or other noxious fluids will be immediately cleaned up and removed to an approved disposal site.

A chemical porta-toilet will be furnished with the drilling rig.

Garbage, trash, and other waste materials will be collected in a portable, self-contained, fully enclosed trash cage during operations. No trash will be burned on location.

All debris and other waste material not contained in the trash cage will be cleaned up and removed from the location immediately after removal of the drilling rig.

Any open pits will be fenced during the operations. The fencing will be maintained until such time as the pits are backfilled.

No chemicals subject to reporting under SARA Title III (hazardous materials) in an amount greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling of this well.

Any produced water from the proposed well will be contained in a water tank and will then be hauled By truck to one of the pre-approved disposal sites: RNI in Sec. 5 T9S R22E, NBU #159 in Sec. 35 T9S R21E, Ace Oilfield in Sec. 2 T6S R20E, MC&MC in Sec. 12 T6S R19E, Pipeline Facility in Sec. 36 T9S R20E, Goat Pasture Evaporation Pond in SW/4 Sec. 16 T10S R22E, Bonanza Evaporation Pond in Sec. 2 T10S R23E.

8. <u>Ancillary Facilities</u>:

None are anticipated.

9. Well Site Layout: (See Location Layout Diagram)

The attached Location Layout Diagram describes drill pad cross-sections, cuts and fills, and locations of the mud tanks, reserve pit, flare pit, pipe racks, trailer parking, spoil dirt stockpile(s), and surface material stockpile(s).

Please see the attached diagram to describe rig orientation, parking areas, and access roads.

The reserve pit will be lined, and when the reserve pit is closed, the pit liner will be buried below plow depth.

All pits will be fenced according to the following minimum standards:

39 inch net wire will be used with at least one strand of barbed wire on top of the net wire. Barbed wire is not necessary if pipe or some type of reinforcement rod is attached to the top of the entire fence.

The net wire shall be no more than two inches above the ground. The barbed wire shall be three inches over the net wire. Total height of the fence shall be at least 42 inches.

Corner posts shall be cemented and/or braced in such a manner to keep the fence tight at all times.

Standard steel, wood, or pipe posts shall be used between the corner braces. Maximum distance between any 2 fence posts shall be no greater than 16 feet.

All wire shall be stretched, by using a stretching device, before it is attached to corner posts.

The reserve pit fencing will be on three sides during drilling operations, and on the fourth side when the rig moves off location. Pits will be fenced and maintained until cleanup.

Location size may change prior to the drilling of the well due to current rig availability. If the proposed location is not large enough to accommodate the drilling rig the location will be resurveyed and a Form 9 shall be submitted.

10. Plans for Reclamation of the Surface:

Producing Location:

Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, materials, trash, and debris not required for production.

Immediately upon well completion, any hydrocarbons in the pit shall be removed in accordance with 43 CFR 3162.7-1.

A plastic, nylon reinforced liner will be used, it shall be torn and perforated before backfilling of the reserve pit.

Before any dirt work associated with location restoration takes place, the reserve pit shall be as dry as possible. All debris in it will be removed. Other waste and spoil materials will be disposed of immediately upon completion of operations.

The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximate natural contours. The reserve pit will be reclaimed within 90 days from the date of well completion, weather permitting.

To prevent surface water(s) from standing (ponding) on the reclaimed reserve pit area, final reclamation of the reserve pit will consist of "mounding" the surface three feet above surrounding ground surface to allow the reclaimed pit area to drain effectively.

Upon completion of backfilling, leveling, and recontouring, the stockpiled topsoil will be spread evenly over the reclaimed area(s).

Dry Hole/Abandoned Location:

Abandoned well sites, roads, and other disturbed areas will be restored as near as practical to their original condition. Where applicable, these conditions include the re-establishment of irrigation systems, the re-establishment of appropriate soil conditions, and re-establishment of vegetation as specified.

All disturbed surfaces will be recontoured to the approximate natural contours, with reclamation of the well pad and access road to be performed as soon as practical after final abandonment. Reseeding operations will be performed after completion of other reclamation operations.

11. Surface/Mineral Ownership:

SITLA 675 East 500 South, Suite 500 Salt Lake City, UT 84102

12. Other Information:

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, the approved Plan of Operations, and any applicable Notice of Lessees. The Operator is fully responsible for the actions of his subcontractors. A copy of these conditions will be furnished to the field representative to ensure compliance.

The Operator will control noxious weeds along Rights-Of-Way for roads, pipelines, well sites, or other applicable facilities.

A Class III archaeological survey report and paleontological survey report is attached.

13. Lessee's or Operators' Representative & Certification:

Kathy Schneebeck Dulnoan Staff Regulatory Analyst Kerr-McGee Oil & Gas Onshore LP PO Box 173779 Denver, CO 80217-3779 (720) 929-6226 Tommy Thompson General Manager, Drilling Kerr-McGee Oil & Gas Onshore LP PO Box 173779 Denver, CO 80217-3779 (720) 929-6724

Certification: All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved Plan of Operations, and any applicable Notice to Lessees.

The Operator will be fully responsible for the actions of its subcontractors. A complete copy of the approved "Application for Permit to Drill" will be furnished to the field representative(s) to ensure compliance and shall be on location during all construction and drilling operations.

Kerr-McGee Oil & Gas Onshore LP is considered to be the operator of the subject well. Kerr-McGee Oil & Gas Onshore LP agrees to be responsible under terms and conditions of the lease for the operations conducted upon leased lands.

Bond coverage pursuant to 43 CFR 3104 for lease activities is being provided by State Surety Bond 22013542.

I hereby certify that I, or persons under my supervision, have inspected the proposed drill site and access route, that I am familiar with the conditions that currently exist; that I have full knowledge of the State and Federal laws applicable to this operation; that the statements made in this plan are, to the best of my knowledge, true and correct; and the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.

Kathy Schnebeck Dulnoan

April 2, 2009

Date

Paleontological Assessment for Anadarko Expansion of Existing Pad for Proposed Wells NBU 922-32F3T (and 922-32L1S, 922-32K1S, 922-32F2S)

Archy Bench Quadrangle
Uintah County, Utah

Prepared for

Anadarko Petroleum Corp.
and
School and Institutional Trust Land
Administration

Prepared by

SWCA Environmental Consultants

1/12/2009 SWCA #UT08-14314-47

Paleontological Assessment for Anadarko Expansion of Existing Pad for Proposed Wells NBU 922-32F3T (and 922-32L1S, 922-32K1S, 922-32F2S)

Prepared for

Anadarko Petroleum Corp.

Granite Tower 1099 18th St. #1200 Denver, CO 80202

and

State of Utah School & Institutional Trust Lands Administration

675 East 500 South, Suite 500 Salt Lake City, UT 84102-2818

Prepared by:

Margaret Imhof M.S., Stephanie M. Lukowski M.S. and Paul C. Murphey, Ph.D. Utah State Permit 07-363

SWCA Environmental Consultants 2028 West 500 North Vernal, UT 84078 Phone: 435.789.9388

Fax: 435.789.9385 www.swca.com

SWCA #UT08-14314-47

1/12/2009

TABLE OF CONTENTS

	Page
1.0 PROJECT SUMMARY	
2.0 INTRODUCTION	2
3.0 METHODS	2
3.1 Personnel	2
3.2 Records Search Methods	2
3.3 Resource Assessment Methods	2
3.4 Field Methods	4
3.5 Distribution of Data	4
4.0 GEOLOGY AND PALEONTOLOGY	4
4.1 Uinta Formation	5
5.0 RESULTS	5
5.1 Previously Documented Localities	6
5.2 Paleontological Sensitivities	6
5.3 Field Survey	
Well Pad Expansion	
6.0 REFERENCES	
<u>Table</u> Table 1. Paleontological Sensitivities of Geologic Units Within the Project APE	<u>Page</u> 6
LIST OF MAPS	
<u>Map</u>	Page
Map 1. Location of Anadarko Petroleum Corp. expansion of existing pad for propo	osed
wells NBU 922-32F3T (and 922-32L1S, 922-32K1S, 922-32F2S)	3
LIST OF FIGURES	
Figure	Dogo
	Page 7
Figure 2. View to the Foot from center stakes.	
Figure 2. View to the East from center stakes	
Figure 5. View to the West from center stakes.	
Figure 5. View to the east of existing well pad from photo point F1-080922-03	δ
LIST OF APPENDICES	
Annendix	

A Fossil Localities Within One Mile of the Project Area of Potential Effect (Confidential)

1.0 PROJECT SUMMARY

- Paleontological assessment conducted at the request of Anadarko Petroleum Corp. and the State of Utah School & Institutional Trust Lands Administration (SITLA). Performed by SWCA Environmental Consultants.
 - O Utah State Permit 07-363
- Paleontological records search and field survey for the expansion of existing pad CIGE #106D for wells NBU 922-32F3T, 922-32L1S, 922-32K1S, and 922-32F2S. Existing access road and pipeline not surveyed.
- Field survey of proposed well pad and access route completed on 9/22/2008 within T9S-R22E-Sec32 SENW in Uintah County, Utah (USGS 7.5 Minute Archy Bench quadrangle).
 - 100-foot survey buffer around well pad.
- Geology
 - Geologic Units (mapped and observed):
 - Lower unit of the Uinta Formation (PFYC Class 5)
- Paleontology
 - Five previously recorded localities within one-mile radius (outside of area of potential effect)
 - No new localities recorded.
- Recommendation
 - Clearance without further mitigation for well pad.
 - However, if any subsurface bones or other potential fossils are encountered during construction anywhere within the project area, work in the immediate vicinity should cease, the SITLA should be notified, and a qualified and Utah State-permitted paleontologist should inspect the location before work continues.
- Distribution of Survey Report
 - Hard copies sent SITLA and Anadarko Petroleum Corp. Hard copy and electronic copies on file at the SWCA Vernal office.

2.0 INTRODUCTION

At the request of Anadarko Petroleum Corp. and the State of Utah School & Institutional Trust Lands Administration (SITLA), SWCA Environmental Consultants conducted a paleontological records search and field survey of the expansion of existing pad CIGE #106D for wells NBU 922-32F3T, 922-32L1S, 922-32K1S, and 922-32F2S. Existing access road and pipeline not surveyed.

The proposed well pad expansion is located in T9S-R22E-Sec32 SENW in Uintah County, Utah (USGS 7.5 Minute Archy Bench quadrangle; See Map 1).

3.0 METHODS

The paleontological survey and evaluation procedures for this assessment were conducted according to State guidelines under Utah State Permit 07-363.

3.1 Personnel


Peter Kloess and Wendi Shaver completed the field survey of the project. Margaret Imhof, M.S., conducted the file searches and Stephanie M. Lukowski, M.S. prepared the final report. Dr. Paul C. Murphey, Principal Investigator on the Utah State permit under which this survey was conducted, supervised the research, field work, and reviewed the final report. Rachel Johnson produced the maps.

3.2 Records Search Methods

Records searches were conducted in order to 1) determine whether any previously recorded fossil localities occur within the project areas; 2) assess the potential for disturbance of these localities during construction; and 3) evaluate the paleontological sensitivity within the area of potential effect (APE). Electronic paleontological records maintained by the Utah Geological Survey, Paleontology Department were searched in order to determine the presence of previously documented fossil localities within the project APE.

3.3 Resource Assessment Methods

The paleontological sensitivity of each geologic unit to be impacted was evaluated using the Potential Fossil Yield Classification System (PFYC), originally developed by the U.S. Forest Service (1996) and recently significantly revised and adopted as policy by the BLM (BLM IM 2008-009) to replace its previous resource management classification system (BLM *Conditions 1-3*). The PFYC utilizes the close relationship between paleontological resource occurrences and the geologic units in which they are preserved. The PFYC designations for the affected geologic units for this project were assigned by the BLM Regional Paleontologist.



Map 1. Location of Anadarko Petroleum Corp. expansion of existing pad for proposed wells NBU 922-32F3T (and 922-32L1S, 922-32K1S, 922-32F2S).

3.4 Field Methods

The survey was designed to 1) determine the surface presence of previously unknown significant vertebrate fossils and/or noteworthy occurrences of invertebrate, plant, or trace fossils; 2) evaluate the condition of documented paleontological localities and the potential for disturbance of these localities during the proposed construction; and 3) evaluate potential adverse impacts to subsurface paleontological resources during construction.

The paleontological field survey consisted of 100-foot-wide buffer around proposed well pad expansion. The area of potential effect was inspected for 1) surface fossils; 2) exposures of potentially fossiliferous rocks; and 3) areas in which fossiliferous rocks will be exposed or otherwise impacted during construction. The survey was 100% pedestrian of outcrop.

A paleontological locality documents the location, identification and description of a scientifically significant fossil(s) along with its geologic context. In addition, however, we record the presence of highly weathered, fragmentary or otherwise unidentifiable fossils as non-significant fossil occurrences which typically consist of fragments of turtle shell, unidentifiable bone and tooth fragments, and unidentifiable plant fossils in order to communicate the presence of fossils in a manner that does not trigger mitigation measures. Typically, fossil locality forms and maps are provided only for significant fossil localities which are either collected at the time of discovery or recommended for avoidance and/or later mitigation.

3.5 Distribution of Data

Copies of this report will be submitted to SITLA and Anadarko Petroleum Corp. Any newly recorded locality data will be submitted to the Utah Geological Survey, State Paleontologist. A hard-copy file will be retained at SWCA Environmental Consultants, Vernal office, along with relevant field notes, maps, and other data. No fossils were collected during this project.

4.0 GEOLOGY AND PALEONTOLOGY

The East-West trending Uinta Mountains were uplifted during the Rocky Mountain-forming Laramide orogeny (Rasmussen et al. 1999) in the Paleocene Epoch (Stokes 1986), exposing the Paleozoic-age rocks in the core of the mountains and Mesozoic-age rocks along their flanks. In conjunction with the uplift, the southerly-adjacent synclinal Uinta Basin formed (Rasmussen et al. 1999). From the Paleocene to the middle Eocene, sediments from freshwater lakes and later from river channels, river deltas and floodplains filled the basin with sediments and accompanying fossils (Stokes 1986, Townsend 2004). From oldest to youngest, these rock units include the Wasatch, Green River, Uinta and Duchesne River formations. Collectively, these units represent the primary source of middle Eocene-aged vertebrate, invertebrate and plant fossils from Utah and Colorado, and are thus of great scientific importance. Locally, Pleistocene- and Holocene-aged sediments deposited by rivers, streams, gravity, and wind overlie the bedrock geologic units.

The project APE contains one mapped geologic unit (Cashion 1973): Eocene-age lower Uinta Formation. In addition to this unit, Holocene-age alluvium and colluvium deposits were also observed during the survey.

4.1 Uinta Formation

In the Uinta Basin, the Uinta Formation consists of greenish-gray, reddish-brown, yellow, grayish-orange, and purple fluvial and lacustrine shale marlstone, siltstone, and sandstone beds which are locally tuffaceous (Cashion 1973; Dane 1954; Rowley et al. 1985). The Uinta Formation is scientifically important because it is the stratotype for the Uintan NALMA and represents nearly all of Uintan time (46.5-40.0 Ma) (Murphey and Evanoff 2007; Townsend 2004; Walsh 1996). In general terms, the Uinta Formation conformably overlies and interfingers with the Green River Formation in the Uinta and Piceance Creek Basins, and is overlain by the Duchesne River Formation in the Uinta Basin. Despite its historical and scientific importance to vertebrate paleontology, the detailed stratigraphy of the Uinta Formation is complex and not yet fully understood.

The Uinta Formation was named by O. C. Marsh in 1871. Based on lithologic differences, O. A Peterson (as quoted in Osborn 1895:72-74) was the first worker to subdivide the Uinta Formation, from stratigraphically lowest to highest, into Horizons A, B, and C. The Wood Committee (Wood et al. 1941) formally divided the Uinta Formation into the older Wagonhound Member (Horizons A and B) and younger Myton Member (Horizon C), and discarded the older tripartite subdivision. However, the older terminology is still widely used because 1) the Wagonhound Member combined two lithologically distinct units: the sandstone-dominated Uinta A, which contains few fossils, and the mudstone and claystone-dominated Uinta B, which contains locally abundant fossils; and 2) fossil collections made prior to the recommendations of the Wood Committee were made using the tripartite scheme. The specific location of the subunit boundaries has shifted slightly with almost each successive publication on the stratigraphy of the area, resulting in a well-understood broad picture for which the stratigraphic details are hazy and the biostratigraphy unresolved (Walsh 1996). The most recent stratigraphic and paleontologic work in the Uinta Formation has included important efforts to better characterize and document the lithostratigraphy, biostratigraphy paleoecology, and paleoenvironments of the Uinta Formation and time-equivalent strata (see Rasmussen et al. 1999; Townsend 2004; Walsh 1996; Townsend et al. 2006).

Approximately 31 percent of modern mammalian families appear in the fossil record of North America during the Uintan NALMA (Black and Dawson 1966). Many of the new taxa are thought to have either originated in North America or emigrated in from Asia (Black and Dawson 1966; Stucky 1992; Beard 1998). The distinctive shift in the composition and diversity of mammalian communities which occurred during the Uintan is marked by the disappearance or decline of more archaic groups such as condylarths, some types of insectivores and marsupials, plesiadapoids, and oxyaenid creodonts. At the same time, more modern groups including lagomorphs, selenodont artiodactyls, advanced carnivorans, and non-ischyromyine rodents began to dominate mammalian communities. See Rasmussen et al. (1999), Townsend (2004), Murphey and Daitch (2007), and Walsh (1996) for further discussions of the mammalian faunas and biostratigraphy of the Uinta Formation.

5.0 RESULTS

The following section presents the results of the records search and field survey conducted for the Anadarko Petroleum Corp. well pad expansion.

5.1 Previously Documented Localities

Five previously documented fossil localities are known within a one-mile radius of the project area. Further information on all the previously recorded localities within a one-mile radius is provided in Appendix A.

5.2 Paleontological Sensitivities

The paleontological sensitivities of the one mapped geologic unit (Cashion 1973) in the project APE has been classified according to the PFYC by the BLM and is summarized in Table 1.

Table 1. Paleontological Sensitivities of Geologic Units Within the Project APE.

Geologic Unit	Map Symbol*	Age	Typical Fossils	PFYC
Uinta Formation, lower part**	Tul	Eocene	Locally abundant plants (leaves, seeds, wood); invertebrates (insects, mollusks); and a highly diverse and scientifically important vertebrate fauna (reptiles, mammals)	Class 5

^{*} Cashion 1973

5.3 Field Survey

NBU 922-32F3T	Well Pad Expansion			
Location:	T9S-R22E-Sec32 SENW			
Surveyed on:	9/22/2008 By: Peter Kloess, Wendi Shaver			
Survey Remarks:	100% pedestrian survey of expansion existing well pad CIGE #106D plus a 100-ft buffer. Existing access road and pipeline not surveyed.			
Photos:	Figures 1-5			
Geologic Formation(s):	Uinta Fm, lower Mbr Eocene PFYC Class 5			
Reference:	Cashion 1973			
Topography:	The existing well pad is flat. A moderate-sized ridge intersects the buffer south of the pit.			
Bedrock Exposure Status: Exposures present along the ridge south of the pit. The remainder of the adisturbed due to the construction of the previous well.				
Geologic Description:	Coarse grained sandstone beds of the Lower Member of the Uinta Formation are present along the moderate sized ridge. Vegetation on top of ridge.			
Fossil Status:	None observed.			
Fossil Description:	N/A			
Recommendation:	Clearance without further mitigation.			
	However, if any subsurface bones or other potential fossils are encountered during construction anywhere within the project area, work in the immediate vicinity should cease, the State should be notified, and a qualified and Utah State-permitted paleontologist should inspect the location <i>before</i> work continues.			



Figure 1. View to the North from center stakes.



Figure 2. View to the East from center stakes.



Figure 3. View to the South from center stakes.



Figure 4. View to the West from center stakes.




Figure 5. View to the east of existing well pad from photo point F1-080922-03.

6.0 REFERENCES

- Beard, K. C. 1998. East of Eden: Asia as an important center of taxonomic origination in mammalian evolution: In: K. C. Beard and M. R. Dawson (eds.): Dawn of the Age of Mammals in Asia, Bulletin of Carnegie Museum of Natural History, no. 34, p. 5-39.
- Black, C. C., and M. R. Dawson. 1966. A review of late Eocene mammalian faunas from North America: American Journal of Science, v. 264, p. 321–349.
- Bureau of Land Management (BLM). 2007. Instructional Memorandum 2008-009, Potential Fossil Resource Classification System.
- Cashion, W. B. 1973. Geologic and structure map of the Grand Junction quadrangle, Colorado and Utah: U.S. Geological Survey, Miscellaneous Geologic Investigations Map I-736 (1:250,000).
- Dane, C. H. 1954. Stratigraphic and facies relationships of upper part of Green River Formation and lower part of Uinta Formation in Duchesne, Uintah, Wasatch Counties, Utah: American Association of Petroleum Geologists Bulletin, v. 38, no. 2, p. 405-425.
- Hail, W. J., Jr., and M. C. Smith. 1994. Geologic map of the northern part of the Piceance Creek Basin, northwestern Colorado: U.S. Geological Survey Map, I-2400.
- Hail, W. J., Jr., and M. C. Smith. 1997. Geologic map of the southern part of the Piceance Creek Basin, northwestern Colorado: U.S. Geological Survey Map, I-2529.
- Murphey, P.C., and Evanoff, E. 2007. Stratigraphy, fossil distribution and depositional environments of the upper Bridger Formation (middle Eocene), southwestern Wyoming: *Wyoming State Geological Survey Report of Investigation 57, 107 p,* (1 map, scale 1:100,000; 10 maps, scale 1:24,000).
- Murphey, P.C., and Daitch, D. 2007. Paleontological overview of oil shale and tar sands areas in Colorado, Utah and Wyoming: U.S. Department of Energy, Argonne National Laboratory Report Prepared for the U.S. Department of Interior Bureau of Land Management, 468 p. and 6 maps (scale 1:500,000).
- Osborn, H. F. 1895. Fossil mammals of the Uinta Basin, Expedition of 1894: Bulletin of the American Museum of Natural History, 7:71-105.
- Rasmussen, D. T., G. C. Conroy, A. R. Friscia, K. E. Townsend, and M. D. Kinkel. 1999. Mammals of the middle Eocene Uinta Formation. In: Gillette, D.E. (ed.). Vertebrate Paleontology in Utah: Utah Geological Survey Miscellaneous Publication, 99-1: 401-420.
- Robinson, P. 1978. Paleontological resources inventory and evaluation, Bureau of Mines Experimental Oil Shale Mine, Rio Blanco County, Colorado: Prepared for VTN Colorado, Inc. 2600 S. Parker Rd., Aurora, Colorado, 22 p.
- Stokes, W. L. 1986. Geology of Utah: Utah Museum of Natural History, University of Utah and Utah Geological and Mineral Survey, Department of Natural Resources.

- Stucky, R. K. 1992. Mammalian faunas in North America of Bridgerian to Arikareean "ages" (Eocene and Oligocene): In: D. R. Prothero and W. A. Berggren (eds.): Eocene-Oligocene Climatic and Biotic Evolution. Princeton, N.J.: Princeton University Press, pp. 463-93.
- Townsend, K. E. 2004. Stratigraphy, paleoecology, and habitat change in the middle Eocene of North America: Unpublished dissertation, Washington University, 418 pp.
- Townsend, K. E., Friscia, A. R., Rasmussen, D. T. 2006. Stratigraphic Distribrution of Upper Middle Eocene Fossil Vertebrate Localities in the Eastern Uinta Basin, Utah, with comments on Uintan Biostratigraphy. The Mountain Geologist, v43, n2, p115-134.
- Walsh, S. L. 1996. Middle Eocene mammalian faunas of San Diego County, California. In: D. R. Prothero and R. J. Emry (eds.): The Terrestrial Eocene-Oligocene Transition in North America. Cambridge: Cambridge University Press: 75-119.
- Wood, H. E., R. W. Chaney, J. Clark, E. H. Colbert, G. L. Jepsen, J. B. Reeside, Jr., and C. Stock. 1941. Nomenclature and correlation of the North American continental Tertiary: Bulletin of the Geological Society of America, 52:1-48.



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office P.O. Box 45155 Salt Lake City, Utah 84145-0155

IN REPLY REFER TO: 3160 (UT-922)

April 17, 2009

Memorandum

To: Assistant District Manager Minerals, Vernal District

From: Michael Coulthard, Petroleum Engineer

Subject: 2009 Plan of Development Natural Buttes Unit

Uintah County, Utah.

Pursuant to email between Diana Whitney, Division of Oil, Gas and Mining, and Mickey Coulthard, Utah State Office, Bureau of Land Management, the following wells are planned for calendar year 2009 within the Natural Buttes Unit, Uintah County, Utah.

API # WELL NAME LOCATION

(Proposed PZ WASATCH-MESA VERDE)

43-047-50342 NBU 922-29M3CS Sec 29 T09S R22E 0572 FSL 0520 FWL BHL Sec 29 T09S R22E 0065 FSL 0315 FWL

43-047-50343 NBU 922-29M2DS Sec 29 T09S R22E 0611 FSL 0511 FWL BHL Sec 29 T09S R22E 0689 FSL 0515 FWL

43-047-50348 NBU 922-32K1S Sec 32 T09S R22E 2137 FNL 1793 FWL

BHL Sec 32 T09S R22E 2558 FSL 2399 FWL

43-047-50349 NBU 922-32F3T Sec 32 T09S R22E 2111 FNL 1824 FWL

43-047-50350 NBU 922-32F2S Sec 32 T09S R22E 2098 FNL 1839 FWL BHL Sec 32 T09S R22E 1558 FNL 1565 FWL

43-047-50351 NBU 922-32E2S Sec 32 T09S R22E 2150 FNL 1778 FWL BHL Sec 32 T09S R22E 1786 FNL 0412 FWL

43-047-38921 NBU 1022-8B-4T Sec 08 T10S R22E 0909 FNL 1793 FEL

This office has no objection to permitting the wells at this time.

/s/ Michael L. Coulthard

bcc: File - Natural Buttes Unit
 Division of Oil Gas and Mining

Central Files
Agr. Sec. Chron
Fluid Chron

MCoulthard:mc:4-17-09

From: Davis, Jim(Jim Davis)

To: Mason, Diana

Date: 4/23/2009 7:37 AM

Subject: Kmg well approvals (8)

CC: Garrison, LaVonne, Bonner, Ed, "White, Raleen" <Raleen.White@anadarko.com>

The following wells have been approved by SITLA including arch and paleo clearance.

NBU 922-32E2S -4304750351 NBU 922-32F2S -4304750350 NBU 922-32F3T - 4304750349 NBU 922-32K1S - 4304750348

BONANZA 1023-2G1BS - 4304750347 BONANZA 1023-2G2CS - 4304750346 BONANZA 1023-2G3BS - 4304750345 BONANZA 1023-2H3CS - 4304750344

-Jim

Jim Davis State of Utah Trust Lands Administration (801) 538-5156

BOPE REVIEW KERR-MCGEE OIL & GAS ONSHORE, L.P. NBU 922-32F3T 43047503490000

Well Name	KERR-MCGEE OIL & GAS ONSHORE, L.P. NBU 922-32F3T 43047503490			
String	Surf	Prod		
Casing Size(")	9.625	4.500		
Setting Depth (TVD)	2300	9200		
Previous Shoe Setting Depth (TVD)	40	2300		
Max Mud Weight (ppg)	8.4	12.0		
BOPE Proposed (psi)	500	5000		
Casing Internal Yield (psi)	3520	7780		
Operators Max Anticipated Pressure (psi)	5244	11.0		


Calculations	Surf String	9.625	"
Max BPH (psi)	.052*Setting Depth*MW=	1005	
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	729	NO
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	499	YES Reasonable Depth in area, No expected pressure
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP22*(Setting Depth - Previous Shoe Depth)=	508	NO Reasonable Depth in area, No expected pressure
Required Casing/BOPE Test Pressure=		2300	psi
*Max Pressure Allowed @	Previous Casing Shoe=	40	psi *Assumes 1psi/ft frac gradient

Calculations	Prod String	4.500	"
Max BPH (psi)	.052*Setting Depth*MW=	5741	
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	4637	YES
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	3717	YES OK
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP22*(Setting Depth - Previous Shoe Depth)=	4223	NO reasonable, note max allowed pressure
Required Casing/BOPE To	est Pressure=	5000	psi
*Max Pressure Allowed @ Previous Casing Shoe=		2300	psi *Assumes 1psi/ft frac gradient

Calculations	String	"
Max BPH (psi)	.052*Setting Depth*MW=	
		BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	NO
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	NO
		*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP22*(Setting Depth - Previous Shoe Depth)=	NO
Required Casing/BOPE To	est Pressure=	psi
*Max Pressure Allowed @ Previous Casing Shoe=		psi *Assumes 1psi/ft frac gradient

Calculations	String	"
Max BPH (psi)	.052*Setting Depth*MW=	
		BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	NO
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	NO
		*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP22*(Setting Depth - Previous Shoe Depth)=	NO
Required Casing/BOPE Te	est Pressure=	psi
*Max Pressure Allowed @	Previous Casing Shoe=	psi *Assumes 1psi/ft frac gradient

43047503490000 NBU 922-32F3T



Well name:

43047503490000 NBU 922-32F3T

Operator:

KERR-MCGEE OIL & GAS ONSHORE, L.P.

String type:

Surface

Project ID:

43-047-50349

Location:

UINTAH

COUNTY

Minimum design factors: **Environment:**

Collapse

Mud weight:

Design parameters:

8.400 ppg Design is based on evacuated pipe.

Collapse:

Design factor 1.125

H2S considered? Surface temperature: No 75 °F

Bottom hole temperature: Temperature gradient:

107 °F 1.40 °F/100ft

Minimum section length: 1,000 ft

Burst:

Design factor

1.00

1.80 (J)

1.80 (J)

2.014 ft

Cement top:

941 ft

Burst

Max anticipated surface

No backup mud specified.

pressure:

2,024 psi 0.120 psi/ft

Internal gradient: Calculated BHP 2,300 psi **Tension:**

8 Round STC: 8 Round LTC:

Buttress: 1.60 (J) Premium: 1.50 (J) 1.60 (B)

Body yield:

Neutral point:

Tension is based on air weight.

Non-directional string.

Re subsequent strings:

Next setting depth: Next mud weight:

9,200 ft 12.000 ppg 5,735 psi

Next setting BHP: Fracture mud wt: Fracture depth: Injection pressure:

19.250 ppg 2,300 ft 2,300 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	2300	9.625	36.00	J-55	LT&C	2300	2300	8.796	18808
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	1004	2020	2.013	2300	3520	1.53	82.8	453	5.47 J

Prepared

Helen Sadik-Macdonald

Div of Oil, Gas & Mining

Phone: 801 538-5357 FAX: 801-359-3940

Date: April 28,2009 Salt Lake City, Utah

Collapse is based on a vertical depth of 2300 ft, a mud weight of 8.4 ppg The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Well name:

43047503490000 NBU 922-32F3T

Operator:

KERR-MCGEE OIL & GAS ONSHORE, L.P.

Production

Project ID:

String type:

Location:

UINTAH COUNTY 43-047-50349

Design parameters:

Collapse

Mud weight: Internal fluid density:

12.000 ppg 2.330 ppg Minimum design factors:

Collapse:

Design factor 1.125 **Environment:**

H2S considered? Surface temperature:

No 75 °F

Bottom hole temperature: 204 °F 1.40 °F/100ft Temperature gradient:

Minimum section length: 1,000 ft

Burst:

Design factor

1.00

1.80 (J)

1.80 (J)

1.60 (J)

Cement top:

Surface

Burst

Max anticipated surface pressure:

Internal gradient: Calculated BHP

3,711 psi 0.220 psi/ft 5,735 psi

No backup mud specified.

8 Round STC: 8 Round LTC: **Buttress:**

> Premium: Body yield:

Tension:

1.50 (J) 1.60 (B)

Tension is based on air weight. Neutral point: 7,550 ft Non-directional string.

Run	Segment		Nominal		End	True Vert	Measured	Drift	Est.
Seq	Length (ft)	Size (in)	Weight (lbs/ft)	Grade	Finish	Depth (ft)	Depth (ft)	Diameter (in)	Cost (\$)
1	9200	4.5	11.60	1-80	LT&C	9200	9200	3.875	121437
Run	Collapse	Collapse	Collapse	Burst	Burst	Burst	Tension	Tension	Tension
Seq	Load (psi)	Strength (psi)	Design Factor	Load (psi)	Strength (psi)	Design Factor	Load (kips)	Strength (kips)	Design Factor
1	4621	6360	1.376	5735	7780	1.36	106.7	212	1.99 J

Prepared

by:

Helen Sadik-Macdonald

Div of Oil, Gas & Mining

Phone: 801 538-5357 FAX: 801-359-3940

Date: April 28,2009 Salt Lake City, Utah

212

1.99 J

Remarks:

Collapse is based on a vertical depth of 9200 ft, a mud weight of 12 ppg An internal gradient of .121 psi/ft was used for collapse from TD to Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

ON-SITE PREDRILL EVALUATION

Utah Division of Oil, Gas and Mining

Operator KERR-MCGEE OIL & GAS ONSHORE, L.P.

Well Name NBU 922-32F3T

API Number 43047503490000 APD No 1395 Field/Unit NATURAL BUTTES

Location: 1/4,1/4 SENW **Sec** 32 **Tw** 9.0S **Rng** 22.0E 2111 FNL 1824 FWL

GPS Coord (UTM) Surface Owner

Participants

Floyd Bartlett and David Hackford (DOGM), Jim Davis (SITLA), Raleen White, Clay Einerson and Tony Kzneck (Kerr McGee) and David Kay (Uintah Engineering and Land Surveying).

Regional/Local Setting & Topography

The proposed gas well is on the existing location of the CIGE 106D gas well. This well is planned to be plugged. Four new wells, NBU 922-32-E2S, NBU 922-32-F2S, NBU 922-32F3T and NBU 922-32K1S are proposed on this pad. The old pit which has been reclaimed will be re-dug and lengthened 40 feet to 90' x 150' x 10' deep. It will be in the southeast corner of the location. The existing pad appears to be stable and should present no problems for drilling and operating the proposed well.

Surface Use Plan

Current Surface Use

Existing Well Pad

New Road Miles Well Pad Src Const Material Surface Formation

Width Length

Ancillary Facilities

Waste Management Plan Adequate?

Environmental Parameters

Affected Floodplains and/or Wetlands

Flora / Fauna

Soil Type and Characteristics

Erosion Issues

Sedimentation Issues

Site Stability Issues

Drainage Diverson Required?

Berm Required?

Erosion Sedimentation Control Required?

Paleo Survey Run? Paleo Potental Observed? Cultural Survey Run? Cultural Resources?

4/30/2009 Page 1

Reserve Pit

Site-Specific Factors	Site Ra	anking	
Distance to Groundwater (feet)	100 to 200	5	
Distance to Surface Water (feet)	>1000	0	
Dist. Nearest Municipal Well (ft)	>5280	0	
Distance to Other Wells (feet)		20	
Native Soil Type	Mod permeability	10	
Fluid Type	Fresh Water	5	
Drill Cuttings	Normal Rock	0	
Annual Precipitation (inches)		0	
Affected Populations			
Presence Nearby Utility Conduits	Not Present	0	
	Final Score	40	1 Sensitivity Level

Characteristics / Requirements

The old pit which has been reclaimed will be re-dug and lengthened 40 feet to 90' x 150' x 10' deep. It will be in the southeast corner of the location.

Closed Loop Mud Required? N Liner Required? Y Liner Thickness 40 Pit Underlayment Required? Y

Other Observations / Comments

Write-up completed 04-14-2009

Floyd Bartlett 6/13/2008
Evaluator Date / Time

4/30/2009 Page 2

Application for Permit to Drill Statement of Basis

Utah Division of Oil, Gas and Mining

APD No	API WellNo	Status	Well Type	Surf Owner	CBM
1395	43047503490000	LOCKED	GW	S	No

Operator KERR-MCGEE OIL & GAS ONSHORE, L.P. Surface Owner-APD

Well Name NBU 922-32F3T Unit NATURAL BUTTES

Field NATURAL BUTTES Type of Work DRILL

Location SENW 32 9S 22E S 2111 FNL 1824 FWL GPS Coord (UTM) 630961E 4428012N

Geologic Statement of Basis

5/6/2009

Kerr McGee proposes to set 2,300' of surface casing at this location. The depth to the base of the moderately saline water at this location is estimated to be at a depth of 3,500'. A search of Division of Water Rights records shows no water wells within a 10,000 foot radius of the center of Section 32. The surface formation at this site is the Uinta Formation. The Uinta Formation is made up of interbedded shales and sandstones. The sandstones are mostly lenticular and discontinuous and should not be a significant source of useable ground water. Production casing cement should be brought up above the base of the moderately saline ground water to isolate it from fresher waters uphole. The proposed casing and cement should adequately protect. Any usable ground water.

Brad Hill 4/15/2009 **APD Evaluator Date / Time**

Surface Statement of Basis

The proposed gas well is on the existing location of the CIGE 106D gas well. This well is planned to be plugged. Four new wells, NBU 922-32-E2S, NBU 922-32-F2S, NBU 922-32F3T and NBU 922-32K1S are proposed on this pad. The old pit which has been reclaimed will be re-dug and lengthened 40 feet to 90' x 150' x 10' deep. It will be in the southeast corner of the location. The existing pad appears to be stable and should present no problems for drilling and operating the proposed well.

Floyd Bartlett 6/13/2008
Onsite Evaluator Date / Time

Conditions of Approval / Application for Permit to Drill

Category Condition

Pits A double synthetic liner each with a minimum thickness of 20 mils and an appropriate thickness of felt sub-liner to cushion

the liners shall be properly installed and maintained in the reserve pit.


Surface The reserve pit shall be fenced upon completion of drilling operations.

Page 1

WORKSHEET APPLICATION FOR PERMIT TO DRILL

APD RECEIVED:	4/13/2009	API NO. ASSIGNED:	43047503490000
WELL NAME:	NBU 922-32F3T		
OPERATOR:	KERR-MCGEE OIL & GAS ONS	HORE, L.P. (N2995) PHONE NUMBER:	720 929-6007
CONTACT:	Kathy Schneebeck-Dulnoan		
PROPOSED LOCATION:	SENW 32 090S 220E	Permit Tech Review:	
SURFACE:	2111 FNL 1824 FWL	Engineering Review:	
воттом:	2111 FNL 1824 FWL	Geology Review:	
COUNTY:	UINTAH		
LATITUDE:	39.99403	LONGITUDE:	-109.46598
UTM SURF EASTINGS:	630961.00	NORTHINGS:	4428012.00
FIELD NAME:	NATURAL BUTTES		
LEASE TYPE:	3 - State		
LEASE NUMBER:	ML 22649	PROPOSED FORMATION:	WSMVD
SURFACE OWNER:	3 - State	COALBED METHANE:	NO
RECEIVED AND/OR REVI	EWED:	LOCATION AND SITING:	
PLAT	LWLD.	R649-2-3.	
	2012542	Unit: NATURAL BUTTES	
P Bond: STATE/FEE - 22	2013542	Unit: NATURAL BUTTES	
Potash		R649-3-2. General	
☑ Oil Shale 190-5			
Oil Shale 190-3		R649-3-3. Exception	
Oil Shale 190-13		Drilling Unit	
✓ Water Permit: Permit	t #43-8496	Board Cause No: Cause 173-14	
RDCC Review:		Effective Date: 12/2/1999	
Fee Surface Agreem	ent	Siting: 460' fr u bdry & uncomm. tract	
Intent to Commingle	e	R649-3-11. Directional Drill	
Commingling Approve	ed		
Comments: Dracita	Completed		
Comments: Presite (Completed		
Stinulations: 5 - Stat	tement of Basis - hhill		

5 - Statement of Basis - bhill 17 - Oil Shale 190-5(b) - dmason 25 - Surface Casing - ddoucet API Well No: 43047503490000



State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER

Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

Permit To Drill

Well Name: NBU 922-32F3T API Well Number: 43047503490000

Lease Number: ML 22649 **Surface Owner:** STATE **Approval Date:** 4/30/2009

Issued to:

KERR-MCGEE OIL & GAS ONSHORE, L.P., P.O. Box 173779, Denver, CO 80217

Authority:

Pursuant to Utah Code Ann. §40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of Cause 173-14.

Duration:

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

General:

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

Conditions of Approval:

In accordance with the Order in Cause No. 190-5(b) dated October 28, 1982, the operator shall comply with the requirements of Rules R649-3-31 and R649-3-27 pertaining to Designated Oil Shale Areas. Additionally, the operators shall ensure that the surface and or production casing is properly cemented over the entire oil shale section as defined by Rule R649-3-31. The Operator shall report the actual depth the oil shale is encountered to the division.

Surface casing shall be cemented to the surface.

Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis (copy attached).

Notification Requirements:

The operator is required to notify the Division of Oil, Gas and Mining of the following action during drilling of this well:

- 24 hours prior to cementing or testing casing contact Dan Jarvis
- 24 hours prior to testing blowout prevention equipment contact Dan Jarvis

API Well No: 43047503490000

- 24 hours prior to spudding the well contact Carol Daniels
- Within 24 hours of any emergency changes made to the approved drilling program contact Dustin Doucet
 - Prior to commencing operations to plug and abandon the well contact Dan Jarvis

The operator is required to get approval from the Division of Oil, Gas and Mining before performing any of the following actions during the drilling of this well:

- Plugging and abandonment or significant plug back of this well contact Dustin Doucet
- Any changes to the approved drilling plan contact Dustin Doucet

The following are Division of Oil, Gas and Mining contacts and their telephone numbers (please leave a voice mail message if the person is not available to take the call):

• Dan Jarvis at: (801) 538-5338 office

(801) 942-0871 home

• Carol Daniels at: (801) 538-5284 office

• Dustin Doucet at: (801) 538-5281 office (801) 733-0983 home

Reporting Requirements:

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

Approved By:

Gil Hunt

Associate Director, Oil & Gas

Die Hunt

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES			FORM 9		
	5.LEASE DESIGNATION AND SERIAL NUMBER: ML 22649				
	RY NOTICES AND REPORTS		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:		
	sals to drill new wells, significantly deepen igged wells, or to drill horizontal laterals. U		7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES		
1. TYPE OF WELL Gas Well			8. WELL NAME and NUMBER: NBU 922-32F3T		
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONS	HORE, L.P.		9. API NUMBER: 43047503490000		
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th S	treet, Suite 600, Denver, CO, 80217 3779	PHONE NUMBER: 720 929-6007 Ext	9. FIELD and POOL or WILDCAT: NATURAL BUTTES		
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2111 FNL 1824 FWL			COUNTY: UINTAH		
QTR/QTR, SECTION, TOWNSHI Qtr/Qtr: SENW Section: 32	(P, RANGE, MERIDIAN: Township: 09.0S Range: 22.0E Meridian:	S	STATE: UTAH		
11. CHE	CK APPROPRIATE BOXES TO INDICAT	E NATURE OF NOTICE, REPORT,	OR OTHER DATA		
TYPE OF SUBMISSION		TYPE OF ACTION			
	_ ACIDIZE	ALTER CASING	CASING REPAIR		
NOTICE OF INTENT Approximate date work will start:	☐ CHANGE TO PREVIOUS PLANS	CHANGE TUBING	CHANGE WELL NAME		
	CHANGE WELL STATUS	COMMINGLE PRODUCING FORMATIONS	CONVERT WELL TYPE		
SUBSEQUENT REPORT Date of Work Completion:	DEEPEN	FRACTURE TREAT	☐ NEW CONSTRUCTION		
	OPERATOR CHANGE	PLUG AND ABANDON	PLUG BACK		
✓ SPUD REPORT	PRODUCTION START OR RESUME	RECLAMATION OF WELL SITE	RECOMPLETE DIFFERENT FORMATION		
Date of Spud: 6/17/2009	REPERFORATE CURRENT FORMATION	SIDETRACK TO REPAIR WELL	TEMPORARY ABANDON		
	☐ TUBING REPAIR	VENT OR FLARE	WATER DISPOSAL		
DRILLING REPORT Report Date:	☐ WATER SHUTOFF	SI TA STATUS EXTENSION	APD EXTENSION		
	☐ WILDCAT WELL DETERMINATION	OTHER	OTHER:		
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. MIRU PETE MARTIN BUCKET RIG. DRILLED 20" CONDUCTOR HOLE TO 40'. RAN 14" 36.7# SCHEDULE 10 PIPE. CMT W/28 SX READY MIX. SPUD WELLAccepted by the LOCATION ON 06/17/2009 AT 1100 HRS. Utah Division of Oil, Gas and Mining FOR RECORD ONLY					
NAME (PLEASE PRINT) Sheila Upchego	PHONE NUMBER 435 781-7024	TITLE Regulatory Analyst			
SIGNATURE N/A		DATE 6/18/2009			

DEPARTMENT OF NATURAL RESIDENCES DIVISION OF OIL, GAS, AND MINING SUNDRY NOTICES AND REPORTS ON WELLS DE not use this form for proposals to drill new wells, significantly deepen existing wells below current button-riched enderly remeter plusgend wells, or to drill howevells, dependently to the control of the control o	STATE OF UTAH		FORM 9			
Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, recenter plugged wells, or to drill hortzontal laterals. Uses APPLICATION FOR PERMIT TO DRILL from for such proposals. 1. TYPE OF WELL SOURCE OF WELL POLISON TO POPERATOR: 2. NAME OF OPERATOR: 3. APP NUMBER: 4. NOCATION OF WELL POUNDAME. 5. NOTICE OF INTERN APPROVED OF ACTION 5. NOTICE OF INTERN CALLED TO ACT OF ACTION 5. NOTICE OF INTERN CALLED TO ACT OF						
Dotton-hole depth, receive plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO NATURAL BUTTOR OF WELL GROWN WILL SAND REPORT OF WELL GROWN WILL SAND REPORT OF WELL GROWN WILL SAND REPORT OF WELL GROWN WILL SAND REPORT OF WELL GROWN WILL GROWN SERVICE STATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA TYPE OF SUBMISSION TYPE OF MATION OF WELL GROWN WILL SAND SAND REPORT OF	SUNDF	RY NOTICES AND REPORTS OF	N WELLS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:		
NBU 92-23-275T	bottom-hole depth, reenter plu	igged wells, or to drill horizontal laterals. Use A				
AADPRESS OF OPERATOR: P.O. Bos 17379 1099 18th Street, Suite 600, Denver, CO, 80217 3779 **ADOTTOR OF WELL P.O. Bos 17379 1099 18th Street, Suite 600, Denver, CO, 80217 3779 **LOCATION OF WELL P.O. Bos 17379 1099 18th Street, Suite 600, Denver, CO, 80217 3779 **LOCATION OF WELL P.O. Bos 17379 1099 18th Street, Suite 600, Denver, CO, 80217 3779 **LOCATION OF WELL P.O. Bos 17379 1099 18th Street, Suite 600, Denver, CO, 80217 3779 **LOCATION OF WELL P.O. Bos 17379 1099 18th Street, Suite 600, Denver, CO, 80217 3779 **LOCATION OF WELL P.O. Bos 17379 1099 18th Street, Suite 600, Denver, CO, 80217 3779 **LOCATION OF WELL P.O. Bos 17379 1099 18th Street, Suite 600, Denver, CO, 80217 3779 **LOCATION OF WELL P.O. Bos 17379 1099 18th Street, Suite 600, Denver, CO, 80217 3779 **LOCATION OF WELL P.O. Bos 17379 1099 18th Street, Suite 600, Denver, CO, 80217 3779 **LOCATION OF WELL P.O. Bos 17379 1099 18th Street, Suite 600, Denver, CO, 80217 3779 **LOCATION OF WELL P.O. Bos 17379 1099 18th Street, Suite 600, Denver, Co, 80217 3779 **LOCATION OF WELL STILL P.O. BOS 17379 1099 18th Street, Suite 600, Denver, Co, 80217 3779 **LOCATION OF WELL STILL P.O. BOS 17379 1099 18th Street, Suite 600, Denver, Co, 80217 18th Street, Suite 600						
P.O. BOX 173779 1099 158H STEET, Suite 600, Denver, CO, 80217 3779 720 929-6007 Ext WITH JUNE AUTITES CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA TYPE OF SUBMISSION TYPE OF ACTION TYPE OF ACTION ACRIDIZE ALTER CASING CHANGE TO PRIVIOUS PLANS ADDITION BEFORE SPUID REPORT Date of South PRODUCTION START OR RESUME PROPERTOR CHANGE PROPERTOR CHANGE PRODUCTION START OR RESUME PROPERTOR CHANGE PROPERTOR CHAN		HORE, L.P.				
POOTLOSE AT SUBFACE: 2111 FIN. 1824 FUIL 2121 FUIL 2121 FIN. 1824 FUIL 2121						
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA TYPE OF SUBMISSION TYPE OF ACTION ACIDIZE	FOOTAGES AT SURFACE:					
TYPE OF SUBMISSION ACIDIZE						
ACIDIZE		CK APPROPRIATE BOXES TO INDICATE N	NATURE OF NOTICE, REPORT,	OR OTHER DATA		
NOTICE OF INTENT Approximate data work will start: GHANGE TO PREVIOUS PLANS CHANGE TUBING CHANGE WELL NAME SUBSEQUENT REPORT Date of Work Completion: DEEPEN PRACTURE TREAT NEW CONSTRUCTION DEEPEN PRACTURE TREAT NEW CONSTRUCTION DEEPEN PRACTURE TREAT NEW CONSTRUCTION DEEPEN PRODUCTION START OR RESUME RECLAMATION OF WELL SITE RECOMPLETE DIFFERENT FORMATION DATE OF SPUID. START OR REPORT NEW CONSTRUCTION PLUG BACK PRODUCTION START OR RESUME RECLAMATION OF WELL SITE RECOMPLETE DIFFERENT FORMATION DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. MIRU PROPERTRO AIR RIG ON 06/22/2009. DRILLED 12 1/4" SURFACE HOLE TO 2340'. RAN 9 5/8" 36# J-55 SURFACE CS. LEAD CMT W/220 SX HIFILIACCEPted by the CLASS G @11.0 PPF 3.82 YIELD. PMP 200 SX PREM CLASS G @15.8 PPG 1.18th Division of YIELD. DROP PLUG ON FLY DISPLACE W/175.5 BBLS OF H20. 20 BBLS OFH 20. 20 B	TYPE OF SUBMISSION		TYPE OF ACTION			
CHANGE WELL STATUS		ACIDIZE	ALTER CASING	CASING REPAIR		
□ SUBSEQUENT REPORT Date of Work Completion: □ OPERATOR CHANGE □ OPERATOR CHANGE □ PLUG AND ABANDON □ PLUG BACK □ PRODUCTION START OR RESUME □ RECLAMATION OF WELL SITE □ RECOMPLETE DIFFERENT FORMATION □ TUSING REPORT Report Date: 6/22/2009 □ WILDCAT WELL DETERMINATION □ TUSING REPORT REPORT SUBJECT STATES STATE STATE STATES STAT	NOTICE OF INTENT Approximate date work will start:	CHANGE TO PREVIOUS PLANS	CHANGE TUBING	CHANGE WELL NAME		
Date of Work Completion: Deteror Deteror Deteror Deteror Change		☐ CHANGE WELL STATUS	COMMINGLE PRODUCING FORMATIONS	CONVERT WELL TYPE		
□ SPUD REPORT □ Date of Spud: □ REPERFORATE CURRENT FORMATION □ REPERFORATE CURRENT FORMATION □ SIDETRACK TO REPAIR WELL □ TUBING REPORT Report Date: □ WATER SHUTOFF □ WILLOAT WELL DETERMINATION □ OTHER □ 12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. MIRU PROPETRO AIR RIG ON 06/22/2009. DRILLED 12 1/4" SURFACE HOLE TO 2340'. RAN 9 5/8" 36# J-55 SURFACE CSG. LEAD CMT W/220 SX HIFILLACcepted by the CLASS G @11.0 PPF 3.82 YIELD. PMP 200 SX PREM CLASS G @15.8 PPG 1.18 Tab Division of YIELD. DROP PLUG ON FLY DISPLACE W/175.5 BBLS OF H2O. 20 BBLS Obil, Gas and Mining LEAD TO SURFACE PLUG DOWN 640 PSI OF LIFT BUMP PLUG 1100 PSI OR RECORD FELL BACK PUMP 150 SX PREM CLASS G @15.8 PPG 1.15 YIELD. 5 GAL 35% CALC PREM CMT DOWN 1" CMT FELL 50' WILL TOP OFF NEXT JOB. WORT. NAME (PLEASE PRINT) Shella Wopsock 435 781-7024 PHONE NUMBER RECUMPLETE DIFFERENT FORMATION REPORTY ABADDON SIDETRACE TORPOR WATER DISPOSAL WATER DISPOSAL WATER DISPOSAL WATER DISPOSAL WATER DISPOSAL WATER DISPOSAL APD EXTENSION OTHER: TUBING REPAIR WATER DISPOSAL APD EXTENSION OTHER: 12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. CHAPTER OF THE PLANT OF		DEEPEN	FRACTURE TREAT	☐ NEW CONSTRUCTION		
Date of Spud: REPERFORATE CURRENT FORMATION SIDETRACK TO REPAIR WELL TEMPORARY ABANDON TUBING REPORT VENT OR FLARE WATER DISPOSAL WATER SHUTOFF SI TA STATUS EXTENSION APD EXTENSION MILOCAT WELL DETERMINATION OTHER 12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. MIRU PROPETRO AIR RIG ON 06/22/2009. DRILLED 12 1/4" SURFACE HOLE TO 2340'. RAN 9 5/8" 36# J-55 SURFACE CSG. LEAD CMT W/220 SX HIFILLACcepted by the CLASS G @11.0 PPF 3.82 YIELD. PMP 200 SX PREM CLASS G @15.8 PPG 1.19tah Division of YIELD. DROP PLUG ON FLY DISPLACE W/175.5 BBLS OF H2O. 20 BBLS OFIL, Gas and Mining LEAD TO SURFACE PLUG DOWN 640 PSI OF LIFT BUMP PLUG 1100 PSITOR RECORD ONLY FELL BACK PUMP 150 SX PREM CLASS G @15.8 PPG 1.15 YIELD. 5 GAL 3% CALC PREM CMT DOWN 1" CMT FELL 50' WILL TOP OFF NEXT JOB. WORT. NAME (PLEASE PRINT)		OPERATOR CHANGE	PLUG AND ABANDON	PLUG BACK		
DRILLING REPORT Report Date: 6/22/2009 DETILING REPORT Report Date: 6/22/2009 DETILING REPORT REPORT DATE: DATE DATE DETILING REPORT REPORT DATE WATER SHUTOFF DATE DATE DATE DATE DATE DATE DATE DATE		☐ PRODUCTION START OR RESUME ☐	RECLAMATION OF WELL SITE	RECOMPLETE DIFFERENT FORMATION		
DRILLING REPORT (6/22/2009) WATER SHUTOFF SITA STATUS EXTENSION APD EXTENSION WILDCAT WELL DETERMINATION OTHER OTHER	Date of Spau.	☐ REPERFORATE CURRENT FORMATION ☐	SIDETRACK TO REPAIR WELL	☐ TEMPORARY ABANDON		
Report Date: 6/22/2009 □ WILDCAT WELL DETERMINATION □ OTHER □ STASTATUS EXTENSION □ OTHER □ OTHER □ OTHER □ OTHER □ OTHER □ WILDCAT WELL DETERMINATION □ OTHER □ OTH	✓ DOTH THE DEPORT	☐ TUBING REPAIR ☐	VENT OR FLARE	WATER DISPOSAL		
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. MIRU PROPETRO AIR RIG ON 06/22/2009. DRILLED 12 1/4" SURFACE HOLE TO 2340'. RAN 9 5/8" 36# J-55 SURFACE CSG. LEAD CMT W/220 SX HIFILLACCEPted by the CLASS G @11.0 PPF 3.82 YIELD. PMP 200 SX PREM CLASS G @15.8 PPG 1.18tah Division of YIELD. DROP PLUG ON FLY DISPLACE W/175.5 BBLS OF H20. 20 BBLS OBIL, Gas and Mining LEAD TO SURFACE PLUG DOWN 640 PSI OF LIFT BUMP PLUG 1100 PSET RECORDONLY FELL BACK PUMP 150 SX PREM CLASS G @15.8 PPG 1.15 YIELD. 5 GAL 3% CALC PREM CMT DOWN 1" CMT FELL 50' WILL TOP OFF NEXT JOB. WORT. NAME (PLEASE PRINT) Shella Wopsock 435 781-7024 PHONE NUMBER REQUIRED TITLE Regulatory Analyst DATE	Report Date:	☐ WATER SHUTOFF	SI TA STATUS EXTENSION	APD EXTENSION		
MIRU PROPETRO AIR RIG ON 06/22/2009. DRILLED 12 1/4" SURFACE HOLE TO 2340'. RAN 9 5/8" 36# J-55 SURFACE CSG. LEAD CMT W/220 SX HIFILLAccepted by the CLASS G @11.0 PPF 3.82 YIELD. PMP 200 SX PREM CLASS G @15.8 PPG 1.10 tah Division of YIELD. DROP PLUG ON FLY DISPLACE W/175.5 BBLS OF H2O. 20 BBLS Ofil, Gas and Mining LEAD TO SURFACE PLUG DOWN 640 PSI OF LIFT BUMP PLUG 1100 PS FOR RECORD ONLY FELL BACK PUMP 150 SX PREM CLASS G @15.8 PPG 1.15 YIELD. 5 GAL 3% CALC PREM CMT DOWN 1" CMT FELL 50' WILL TOP OFF NEXT JOB. WORT. NAME (PLEASE PRINT) Sheila Wopsock 435 781-7024 PHONE NUMBER Regulatory Analyst SIGNATURE DATE	0/22/2009	□ WILDCAT WELL DETERMINATION □	OTHER	OTHER:		
Sheila Wopsock 435 781-7024 Regulatory Analyst SIGNATURE DATE	MIRU PROPETRO AIR RIG ON 06/22/2009. DRILLED 12 1/4" SURFACE HOLE TO 2340'. RAN 9 5/8" 36# J-55 SURFACE CSG. LEAD CMT W/220 SX HIFILIAccepted by the CLASS G @11.0 PPF 3.82 YIELD. PMP 200 SX PREM CLASS G @15.8 PPG 1.18tah Division of YIELD. DROP PLUG ON FLY DISPLACE W/175.5 BBLS OF H2O. 20 BBLS OF II, Gas and Mining LEAD TO SURFACE PLUG DOWN 640 PSI OF LIFT BUMP PLUG 1100 PSITOR RECORD ONLY FELL BACK PUMP 150 SX PREM CLASS G @15.8 PPG 1.15 YIELD. 5 GAL 3%					
SIGNATURE DATE						
	SIGNATURE	.55 /01 /02	DATE			

	STATE OF UTAH		FORM 9
	DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MININ	NG	5.LEASE DESIGNATION AND SERIAL NUMBER: ML 22649
SUND	RY NOTICES AND REPORTS O	N WELLS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
Do not use this form for propos bottom-hole depth, reenter plu DRILL form for such proposals.	sals to drill new wells, significantly deepen ex igged wells, or to drill horizontal laterals. Use	isting wells below current APPLICATION FOR PERMIT TO	7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES
1. TYPE OF WELL Gas Well			8. WELL NAME and NUMBER: NBU 922-32F3T
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSI		9. API NUMBER: 43047503490000	
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th S	treet, Suite 600, Denver, CO, 80217 3779	PHONE NUMBER: 720 929-6007 Ext	9. FIELD and POOL or WILDCAT: NATURAL BUTTES
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2111 FNL 1824 FWL			COUNTY: UINTAH
QTR/QTR, SECTION, TOWNSHI Qtr/Qtr: SENW Section: 32	(P, RANGE, MERIDIAN: Township: 09.0S Range: 22.0E Meridian: S		STATE: UTAH
11. CHE	CK APPROPRIATE BOXES TO INDICATE	NATURE OF NOTICE, REPORT,	OR OTHER DATA
TYPE OF SUBMISSION		TYPE OF ACTION	
Kerr-McGee Oil & Ga this pad for comple requirements in the C KMG is also reques other completion op skim tanks placed or before the water is tanks is to collect any other completion op	DIPPLETED OPERATIONS. Clearly show all perting is Onshore, LP is requesting to retion operations. The refurb pit COA of the APD. Upon completion ting to utilize this pit as a staging perations in the area. There will not location. The trucks will unload a placed into the refurbed pit. They have corations before releasing into the art. During this time the attache	refurb the existing pit on will be relined per the n of the wells on this pading pit to be utilized for be 2 - 400 bbl upright d water into these tank be purpose of the skim been associated with the pit. We plan to keep	Approved by the Utah Division of Oil, Gas and Mining ate: September 22, 2009 y: Italian in the september 22 in fluids will be recycled in this
NAME (PLEASE PRINT)	PHONE NUMBER	TITLE	
Raleen White SIGNATURE	720 929-6666	Sr. Regulatory Analyst DATE	
N/A		9/14/2009	



The Utah Division of Oil, Gas, and Mining

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

Sundry Conditions of Approval Well Number 43047503490000

A synthetic liner with a minimum thickness of 30 mils shall be properly installed and maintained in the pit.

Approved by the Utah Division of Oil, Gas and Mining

Date: September 22, 2009

Rv:

	STATE OF UTAH		FORM 9									
	DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING	3	5.LEASE DESIGNATION AND SERIAL NUMBER: ML 22649									
SUNDF	RY NOTICES AND REPORTS ON	I WELLS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:									
	sals to drill new wells, significantly deepen exist igged wells, or to drill horizontal laterals. Use Al		7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES									
1. TYPE OF WELL Gas Well	8. WELL NAME and NUMBER: NBU 922-32F3T											
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSI	HORE, L.P.		9. API NUMBER: 43047503490000									
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th S	treet, Suite 600, Denver, CO, 80217 3779	PHONE NUMBER: 720 929-6007 Ext	9. FIELD and POOL or WILDCAT: NATURAL BUTTES									
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2111 FNL 1824 FWL			COUNTY: UINTAH									
QTR/QTR, SECTION, TOWNSHI Qtr/Qtr: SENW Section: 32	(P, RANGE, MERIDIAN: Township: 09.0S Range: 22.0E Meridian: S		STATE: UTAH									
11. CHE	CK APPROPRIATE BOXES TO INDICATE NA	ATURE OF NOTICE, REPORT,	OR OTHER DATA									
TYPE OF SUBMISSION		TYPE OF ACTION										
	☐ ACIDIZE ☐ /	ALTER CASING	CASING REPAIR									
☐ NOTICE OF INTENT	CHANGE TO PREVIOUS PLANS	CHANGE TUBING	CHANGE WELL NAME									
Approximate date work will start:	☐ CHANGE WELL STATUS	COMMINGLE PRODUCING FORMATIONS	☐ CONVERT WELL TYPE									
SUBSEQUENT REPORT Date of Work Completion:	☐ DEEPEN ☐ I	FRACTURE TREAT	☐ NEW CONSTRUCTION									
Date of Work Completion:	OPERATOR CHANGE	PLUG AND ABANDON	PLUG BACK									
_		RECLAMATION OF WELL SITE	RECOMPLETE DIFFERENT FORMATION									
SPUD REPORT Date of Spud:		SIDETRACK TO REPAIR WELL	TEMPORARY ABANDON									
			WATER DISPOSAL									
✓ DRILLING REPORT		VENT OR FLARE										
Report Date: 9/28/2009		SI TA STATUS EXTENSION	APD EXTENSION									
3, 20, 2003	☐ WILDCAT WELL DETERMINATION ☐ ☐ (OTHER	OTHER:									
9/28/2009 WILDCAT WELL DETERMINATION OTHER 12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. FINISHED DRILLING FROM 2,340' TO 9,282' ON 09/27/2009. RAN 4-1/2" 11.6# I-80 PRODUCTION CSG. PUMP 40 BBLS H20. LEAD CMT W/578 SX Accepted by the CLASS G PREM LITE @ 12.2 PPG, 2.17 YIELD. TAILED CMT W/1140 SX CLAS \$\mathbf{U}\$ and \$\mathbf{D}\$ ivision of G 50/50 POZ @ 14.3 PPG, 1.31 YIELD. DROP PLUG & DISPLACE W/143. \$\mathbf{D}\$ ii, \$\mathbf{G}\$ as and \$\mathbf{M}\$ ining BBLS H20 + ADDITIVES. GOOD RETURNS THROUGHOUT JOB. LIFTOR RECORD PRESSURE @ 2800 PSI. BUMP PLUG W/3300 PSI & 40 BBLS CMT TO PIT. HOLD 5 MINUTES W/ NO LOSS, PLUG DOWN. FLOATS HELD W/2.0 BBLS BACK TO INVENTORY. RELEASE H&P 298 RIG ON 09/28/2009 AT 20:30 HRS.												
NAME (PLEASE PRINT) Andy Lytle	PHONE NUMBER 720 929-6100	TITLE Regulatory Analyst										
SIGNATURE N/A		DATE 9/29/2009										

	STATE OF UTAH		FORM 9
	DEPARTMENT OF NATURAL RESOURCE DIVISION OF OIL, GAS, AND MI		5.LEASE DESIGNATION AND SERIAL NUMBER: ML 22649
	RY NOTICES AND REPORTS		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
	sals to drill new wells, significantly deepe ugged wells, or to drill horizontal laterals.		7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES
1. TYPE OF WELL Gas Well	8. WELL NAME and NUMBER: NBU 922-32F3T		
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONS	HORE, L.P.		9. API NUMBER: 43047503490000
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th S	treet, Suite 600, Denver, CO, 80217 377	PHONE NUMBER: 720 929-6007 Ext	9. FIELD and POOL or WILDCAT: NATURAL BUTTES
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2111 FNL 1824 FWL			COUNTY: UINTAH
QTR/QTR, SECTION, TOWNSHI Qtr/Qtr: SENW Section: 32	IP, RANGE, MERIDIAN: Township: 09.0S Range: 22.0E Meridian	: S	STATE: UTAH
11. CHE	CK APPROPRIATE BOXES TO INDICA	TE NATURE OF NOTICE, REPORT,	OR OTHER DATA
TYPE OF SUBMISSION		TYPE OF ACTION	
_	ACIDIZE	ALTER CASING	CASING REPAIR
NOTICE OF INTENT Approximate date work will start:	CHANGE TO PREVIOUS PLANS	CHANGE TUBING COMMINGLE PRODUCING FORMATIONS	CHANGE WELL NAME
SUBSEQUENT REPORT	☐ CHANGE WELL STATUS	FRACTURE TREAT	☐ CONVERT WELL TYPE ☐ NEW CONSTRUCTION
Date of Work Completion:	OPERATOR CHANGE	☐ PLUG AND ABANDON	☐ PLUG BACK
SPUD REPORT	✓ PRODUCTION START OR RESUME	RECLAMATION OF WELL SITE	RECOMPLETE DIFFERENT FORMATION
Date of Spud:	REPERFORATE CURRENT FORMATION	SIDETRACK TO REPAIR WELL	☐ TEMPORARY ABANDON
	☐ TUBING REPAIR	☐ VENT OR FLARE	WATER DISPOSAL
✓ DRILLING REPORT Report Date:	☐ WATER SHUTOFF	SI TA STATUS EXTENSION	APD EXTENSION
1/15/2010	☐ WILDCAT WELL DETERMINATION	OTHER	OTHER:
THE SUBJECT WELL V	MPLETED OPERATIONS. Clearly show all per VAS PLACED ON PRODUCTIO ICAL WELL HISTORY WILL BE COMPLETION REPORT	N ON 01/15/2010 AT 12:00 SUBMITTED WITH WELL A Oi)
NAME (PLEASE PRINT) Andy Lytle	PHONE NUMBE 720 929-6100	R TITLE Regulatory Analyst	
SIGNATURE N/A		DATE 1/21/2010	

				RTMEN		ATURA	L RESC	OURCE:	_			(hi	ghlight	REPOI changes	5)	F	FORM 8
													ML 22	649			
WEL	L COM	PLET	ION	OR F	RECC	MPL	ETIC	ON R	EPOF	RT ANI	LOG	6. II	F INDIAN,	ALLOTTE	€ OR TF	RIBE NAME	
1a. TYPE OF WELL		OI W	ELL C] {	GAS F WELL W	Z	DRY		ОТН	ER		- [UTU6	AGREEM 3047A		ME	
b. TYPE OF WORK NEW WELL	C: HORIZ. LATS.	DE EN	EP-] [RE- ENTRY [DIFF. RESVR.		ОТН	ER				NE and NUI 122-32			
2. NAME OF OPERA		& GA	S ON:	SHOR	FIP								PI NUMBI	ER: 50349			
3. ADDRESS OF OF	PERATOR:										NUMBER:	10 F	IELD AND	POOL, O	R WILD		
P.O. BOX 1			ITY DE	NVER	₹	STATE	CO	ZIP 80 2	217	(72	929-6100			RAL B			IOF
AT SURFACE:	SENW 2	2111 F												32		nship, ran 22E	GE,
AT TOP PRODU		AL REPOR	KIED BEI	LOW:								12.	COUNTY		\neg	13. STATE	
14. DATE SPUDDE		DATE T.	D BEAC	UED:	16 DAT	E COMPL	ETED:					l	JINTA		(DE DI	D. DT. OU.	UTAH
6/21/2009		9/27/2		HED.		5/2010			ABANDON	ED 🗌	READY TO PRODU	CE 🗸		003' GI		B, RT, GL):	
18. TOTAL DEPTH:	TVD 9.2	82		19. PLUG		TVD	9,235 9,235		20. IF N	MULTIPLE CO	OMPLETIONS, HOW	/ MANY? *		TH BRIDG UG SET:	GE MC		
22. TYPE ELECTRIC	GR-SDL			,	Submit cop	oy of each)			WAS DST	L CORED? RUN? NAL SURVEY?	NO NO NO	<u>✓</u>	YES	(Sub	omit analysis	ş)
24. CASING AND L	NER RECORD) (Report a	ali strings	s set in we	=II)	·			·	DIRECTIO	NAL SURVET?	NO	V	YES	(Sui	omit copy)	
HOLE SIZE	SIZE/GRA	DE	WEIGHT	(#/ft.)	TOP	(MD)	вотто	PM (MD)		EMENTER	CEMENT TYPE & NO. OF SACKS	SLU		CEMEN.	T TOP *	* AMOU	NT PULLED
20"	14" \$	STL	36.7				4	0			28						
12 1/4"		J-55	36				_	341			570						
7 7/8"	4 1/2	I-80	11.6	5#			9,2	272			1718	<u> </u>					
																 	
25. TUBING RECOR	RD								J			<u></u>					
SIZE	DEPTH S	ET (MD)	PACKI	ER SET (N	/ID)	SIZE		DEPTH	SET (MD)	PACKE	R SET (MD)	SIZE	D	EPTH SET	r (MD)	PACKER	R SET (MD)
2 3/8"	8.5	68															
26. PRODUCING IN		TOP ((MD)	вотто	M (MID)	TOP	(T) (D)	вотто			L (Top/Bot - MD)	0175	NO UO	F0.T	BEBEG	DATION OT	
(A) WASATCI		7,0			04	101	(140)	ВОТТО	WI(IVD)	7,066	7,104	0.36	NO. HOL	Oper		RATION ST Squeezed	
(B) MESAVEI		<u> </u>	70		116					7,170	9,116	0.36	147		=	Squeezed	=
(C)				0,					• •	.,,,,	0,110	0.00	1-77	Oper	=	Squeezed	=-
(D)														Oper	一	Squeezed	一一
28. ACID, FRACTUR	E, TREATME	NT, CEME	NT SQUE	EZE, ETC).												
DEPTHI	NTERVAL								AMO	DUNT AND T	YPE OF MATERIAL						
7,066-7,267			PMP	2,052	BBL	SSLIC	K H2	0 & 98	,208 L	BS 30/5	0 SD.						
7,411-9,116			PMP	10,24	2 BBI	S SL	СК Н	20 & 3	95,299	LBS 30	0/50 SD.						
										=							
	RICAL/MECHA			0514515		- 1011			C REPORT	=	DST REPORT	DIREC	TIONAL S			PRO	
LJ SUNDR	Y NOTICE FOI	n rluggi	NG AND	CEIVIENI	VERIFICA	ATION	<u> </u>	CORE AN	ALTSIS	<u> </u>	OTHER:	R	ECE	IVE	D —		
5/2000)							(CO	NTINUE	D ON B	ACK)		FE	B 1 i	IVE	ン) .		

31. INITIAL PRO	ODUCTION					INTE	ERVAL A (As show	wn in item #26)					
DATE FIRST PR 1/15/2010		7EST 0	ATE: 2010	·		HOURS TESTED): ?4	TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF: 2,803	WATER - 1		PROD. METHOD: FLOWING
сноке size: 18/64	твс. pres 1,500		RESS. 100	API GRA	VITY	BTU GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL: 80	GAS MCF: 2,803	WATER - 1 280		INTERVAL STATUS: PROD
						INTI	ERVAL B (As sho	wn in item #26)					
DATE FIRST PR	RODUCED:	TEST D	ATE:			HOURS TESTED);	TEST PRODUCTION RATES: →	OIL BBL:	GAS – MCF:	WATER I	BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRES	S. CSG. P	RESS.	API GRA	VITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS - MCF:	WATER - I	BBL:	INTERVAL STATUS:
		<u> </u>		•		INT	ERVAL C (As show	wn in item #26)			•		•
DATE FIRST PR	RODUCED:	TEST D	ATE:			HOURS TESTED):	TEST PRODUCTION RATES: →	OIL – BBL:	GAS - MCF:	WATER - I	BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRES	S. CSG. P	RESS.	API GRA	VITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS - MCF:	WATER - I	BBL:	INTERVAL STATUS:
	- !					INTE	ERVAL D (As show	vn in item #26)			·•·		1
DATE FIRST PR	RODUCED:	TEST C	ATE:			HOURS TESTED	:	TEST PRODUCTION RATES: →	OIL – BBL:	GAS - MCF:	WATER - I	BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRES	S. CSG. P	RESS.	API GRA	VITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS MCF:	WATER - I	BBL:	INTERVAL STATUS:
32. DISPOSITIO	ON OF GAS (S	old, Used for	Fuel, Ve	ented, Etc.))								
33. SUMMARY	OF POROUS	ZONES (Inclu	de Aquif	fers):				34	. FORMATION	(Log) MARKERS:			
Show all importa tested, cushion u							tests, including de	pth interval					
Formation	on	Top (MD)		ottom MD)		Descript	ions, Contents, etc			Name		(N)	Top //easured Depth)

GREEN RIVER 1,304 **MAHOGANY** 1,978 **WASATCH** 4,557 7,147 9,248 **MESAVERDE** 7,147

35. ADDITIONAL REMARKS (Include plugging procedure)

ATTACHED TO THIS COMPLETION REPORT IS THE CHRONOLOGICAL WELL HISTORY AND EOWR.

NAME (PLEASE PRINT) ANDY LYTLE SIGNATURE TITLE REGULATORY ANALYST DATE 2/12/2010	36. I hereby certify that the foregoing and attached information is complete and correct as determined fr	om all avail	able records.
1/12/2010	NAME (PLEASE PRINT) ANDY LYTLE	TITLE	REGULATORY ANALYST
	$\Lambda \sim \rho$	DATE	2/12/2010

This report must be submitted within 30 days of

- completing or plugging a new well
- drilling horizontal laterals from an existing well bore
- recompleting to a different producing formation
- reentering a previously plugged and abandoned well
- significantly deepening an existing well bore below the previous bottom-hole depth
- drilling hydrocarbon exploratory holes, such as core samples and stratigraphic tests

* ITEM 20: Show the number of completions if production is measured separately from two or more formations.

** ITEM 24: Cement Top - Show how reported top(s) of cement were determined (circulated (CIR), calculated (CAL), cement bond log (CBL), temperature survey (TS)).

Send to: Utah Division of Oil, Gas and Mining

1594 West North Temple, Suite 1210

Box 145801

Salt Lake City, Utah 84114-5801

Phone: 801-538-5340

Fax: 801-359-3940

General General

1.1 Customer Information

Company	US ROCKIES REGION
Representative	
Address	

1.2 Well Information

Well	NBU 922-32F3T [BLUE]	Wellbore No.	ОН
Well Name	NBU 922-32F3T	Common Name	NBU 922-32F3T
Project	UTAH-UINTAH	Site	NBU 922-32F PAD
Vertical Section Azimuth		North Reference	True
Origin N/S		Origin E/W	
Spud Date	6/21/2009	UWI	0/9/S/22/E/32/0/SWSENW/26/PM/N/2,111.00/ W/0/1,824.00/0/0
Active Datum	RKB @5,029.00ft (above Mean Sea L	evel)	

2 Survey Name

2.1 Survey Name: Survey #1

Survey Name	Survey #1	Company	SCIENTIFIC
Started	6/21/2009	Ended	
Tool Name	MWD	Engineer	Anadarko

2.1.1 Tie On Point

	그들이 있다. 아이들의 아이들은 그런 사람들은 사람들은 사람이 아니는 것은 가장 나를 모든 것이다.	nc °)	Azi (°)	TVD (ft)	N/S (ft)	E/W (ft)
Ĺ	26.00	0.00	0.00	26.00	0.00	0.00

2.1.2 Survey Stations

Date	Type	MD (ft)	Inc (°)	Azi (°)	TVD (ft)	N/S (ft)	E/W (ft)	V. Sec (ft)	DLeg (°/100ft)	Build (°/100ft)	Turn (°/100ft)	TFace
6/21/2009	Tie On	26.00	0.00	0.00	26.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
6/21/2009	NORMAL	196.00	0.20	327.00	196.00	0.25	-0.16	0.25	0.12	0.12	0.00	327.00
	NORMAL	286.00	0.28	245.00	286.00	0.29	-0.45	0.29	0.36	0.09	-91.11	-120.15
	NORMAL	376.00	0.34	286.00	376.00	0.27	-0.90	0.27	0.25	0.07	45.56	95.99
	NORMAL	646.00	0.42	127.00	646.00	-0.14	-1.01	-0.14	0.33	0.17	-50.00	-84.81
	NORMAL	736.00	0.07	170.00	735.99	-0.39	-0.73	-0.39	0.41	-0.39	47.78	172.62
	NORMAL	856.00	0.37	112.00	855.99	-0.61	-0.36	-0.61	0.28	0.25	-48.33	-68.11
	NORMAL	976.00	0.65	117.00	975.99	-1.06	0.61	-1.06	0.24	0.23	4.17	11.54
	NORMAL	1,096.00	0.85	119.00	1,095.98	-1.80	1.99	-1.80	0.17	0.17	1.67	8.46
	NORMAL	1,216.00	0.52	153.00	1,215.97	-2.72	3.02	-2.72	0.42	-0.27	28.33	145.23
	NORMAL	1,336.00	0.48	84.00	1,335.97	-3.15	3.76	-3.15	0.47	-0.03	-57.50	-127.83
	NORMAL	1,456.00	0.44	35.80	1,455.96	-2.72	4.53	-2.72	0.31	-0.03	-40.17	-119.65
	NORMAL	1,576.00	0.58	7.77	1,575.96	-1.75	4.88	-1.75	0.23	0.12	-23.36	-75.21
	NORMAL	1,696.00	0.31	329.00	1,695.95	-0.87	4.80	-0.87	0.33	-0.23	-32.31	-150.15
	NORMAL	1,816.00	0.44	347.75	1,815.95	-0.14	4.53	-0.14	0.15	0.11	15.63	52.98
	NORMAL	1,936.00	0.30	248.20	1,935.95	0.19	4.14	0.19	0.48	-0.12	-82.96	-148.87
6/21/2009	NORMAL	466.00	0.14	310.00	466.00	0.41	-1.24	0.41	0.24	-0.22	26.67	164.97
6/21/2009	NORMAL	556.00	0.27	172.00	556.00	0.27	-1.30	0.27	0.43	0.14	-153.33	-152.06
6/22/2009	NORMAL	2,056.00	0.54	216.32	2,055.95	-0.38	3.52	-0.38	0.27	0.20	-26.57	-60.93
***************************************	NORMAL	2,176.00	0.61	202.38	2,175.94	-1.42	2.94	-1.42	0.13	0.06	-11.62	-70.50

2.1.2 Survey Stations (Continued)

Date	Type	MD (ft)	Inc (°)	Azi (°)	TVD (ft)	N/S (ft)	E/W (ft)	V. Sec (ft)	DLeg (°/100ft)	Build (°/100ft)	Turn (°/100ft)	TFace (°)
6/22/2009	NORMAL	2,296.00	0.53	208.62	2,295.94	-2.50	2.43	-2.50	0.08	-0.07	5.20	145.28
	NORMAL	2,326.00	0.79	195.58	2,325.93	-2.82	2.31	-2.82	1.00	0.87	-43.47	-36.64

2.2 Survey Name: Survey #2

Survey Name	Survey #2	Company	WEATHERFORD
Started	9/23/2009	Ended	
Tool Name		Engineer	Anadarko

2.2.1 Tie On Point

MD	Inc	Azi	TVD	N/S	E/W
(ft)	(°)	(°)	(ft)	(ft)	(ft)
2,322.00	0.79	195.58	2,322.00	-2.80	2.27

2.2.2 Survey Stations

Date	Туре	MD	inc	Azi	TVD	N/S	E/W	V. Sec	DLeg	Build	Turn	TFace
		(ft)	(°)	<u>(°)</u>	(ft)	(ft)	(ft)	(ft)	(°/100ft)	(°/100ft)	(°/100ft)	(°)
9/23/2009	å	2,322.00	0.79	195.58	2,322.00	-2.80	2.27	-2.80	0.00	0.00	0.00	0.00
9/23/2009	V	2,381.00	0.69	220.11	2,381.00	-3.46	1.93	-3.46	0.56	-0.17	41.58	119.53
	NORMAL	2,570.00	1.00	210.94	2,569.97	-5.75	0.35	-5.75	0.18	0.16	-4.85	-28.20
	NORMAL	2,758.00	0.50	257.06	2,757.96	-7.34	-1.29	-7.34	0.40	-0.27	24.53	151.12
	NORMAL	2,948.00	1.13	230.19	2,947.94	-8.72	-3.54	-8.72	0.38	0.33	-14.14	-45.15
9/24/2009	A	3,138.00	1.06	296.44	3,137.91	-9.14	-6.55	-9.14	0.63	-0.04	34.87	125.92
	NORMAL	3,327.00	0.49	355.78	3,326.90	-7.56	-8.18	-7.56	0.48	-0.30	31.40	152.51
	NORMAL	3,517.00	0.88	12.31	3,516.88	-5.32	-7.93	-5.32	0.23	0.21	8.70	35.30
	NORMAL	3,707.00	0.88	3.56	3,706.86	-2.44	-7.52	-2.44	0.07	0.00	-4.61	-94.37
	NORMAL	3,896.00	0.63	329.06	3,895.84	-0.10	-7.97	-0.10	0.27	-0.13	-18.25	-135.32
	NORMAL	4,086.00	0.31	42.56	4,085.84	1.17	-8.16	1.17	0.33	-0.17	38.68	151.26
	NORMAL	4,276.00	0.56	42.06	4,275.83	2.24	-7.19	2.24	0.13	0.13	-0.26	-1.12
	NORMAL	4,465.00	0.25	72.94	4,464.83	3.05	-6.18	3.05	0.19	-0.16	16.34	159.62
	NORMAL	4,654.00	0.31	22.06	4,653.83	3.64	-5.59	3.64	0.13	0.03	-26.92	-102.75
	NORMAL	4,843.00	1.31	348.56	4,842.81	6.24	-5.83	6.24	0.56	0.53	-17.72	-42.74
	NORMAL	5,033.00	0.56	21.19	5,032.78	9.23	-5.92	9.23	0.47	-0.39	17.17	160.19
	NORMAL	5,222.00	1.50	73.81	5,221.75	10.78	-3.21	10.78	0.66	0.50	27.84	73.60
	NORMAL	5,410.00	1.06	86.19	5,409.70	11.58	0.89	11.58	0.28	-0.23	6.59	153.94
	NORMAL	5,598.00	0.72	316.56	5,597.69	12.56	1.81	12.56	0.86	-0.18	-68.95	-159.95
****	NORMAL	5,787.00	0.25	258.19	5,786.69	13.33	0.59	13.33	0.33	-0.25	-30.88	-160.13
	NORMAL	5,977.00	0.06	258.19	5,976.69	13.23	0.09	13.23	0.10	-0.10	0.00	180.00
	NORMAL	6,165.00	0.56	135.81	6,164.68	12.55	0.63	12.55	0.32	0.27	-65.10	-127.27
9/25/2009	NORMAL	6,355.00	0.69	359.31	6,354.68	13.03	1.26	13.03	0.61	0.07	-71.84	-155.87
	NORMAL	6,544.00	2.13	325.19	6,543.62	17.05	-0.75	17.05	0.85	0.76	-18.05	-48.06
	NORMAL	6,733.00	1.38	319.94	6,732.53	21.68	-4.22	21.68	0.41	-0.40	-2.78	-170.52
	NORMAL	6,921.00	0.69	261.94	6,920.50	23.25	-6.80	23.25	0.62	-0.37	-30.85	-150.02
	NORMAL	7,111.00	0.69	236.06	7,110.49	22.45	-8.88	22.45	0.16	0.00	-13.62	-102.94
	NORMAL	7,301.00	0.50	205.69	7,300.48	21.06	-10.19	21.06	0.19	-0.10	-15.98	-135.65
and the same of the same of the	NORMAL	7,490.00	0.63	161.69	7,489.47	19.34	-10.22	19.34	0.23	0.07	-23.28	-96.10
	NORMAL	7,680.00	1.06	159.19	7,679,45	16.70	-9.27	16.70	0.23	0.23	-1.32	-6.15
9/26/2009	NORMAL	7,879.00	1.63	148.69	7,878.39	12.56	-7.15	12.56	0.31	0.29	-5.28	-28.69
	NORMAL	8,059.00	1.38	120.94	8,058.33	9.26	-3.96	9.26	0.42	-0.14	-15.42	-122.46
	NORMAL	8,248.00	0.69	242.44	8,247.32	7.56	-3.01	7.56	0.97	-0.37	64.29	161.32
	NORMAL	8,438.00	0.94	203.69	8,437.30	5.61	-4.65	5.61	0.31	0.13	-20.39	-85.81
	NORMAL	8,626.00	1.13	177.81	8,625.27	2.34	-5.20	2.34	0.27	0.10	-13.77	-81.16
	NORMAL	8,816.00	1.75	180.81	8,815.21	-2.43	-5.17	-2.43	0.33	0.33	1.58	8.43
make the contract of the contr	NORMAL	9,004.00	1.81	170.19	9,003.12	-8.23	-4.71	-8.23	0.18	0.03	-5.65	-85.03

2.2.2 Survey Stations (Continued)

Date Type	MD	Inc	Azi	TVD	N/S	E/W	V. Sec	DLeg	Build	Turn	TFace
	(ft)	(°)	(°)	(ft)	(ft)	(ft)	(ft)	(°/100ft)	(°/100ft)	(°/100ft)	(°)
9/27/2009 NORMAL	9,231.00	2.22	164.06	9,229.98	-15.99	-2.89	-15.99	0.20	0.18	-2.70	-30.82

	STATE OF UTAH		FORM 9
	5.LEASE DESIGNATION AND SERIAL NUMBER: ML 22649		
SUND	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:		
	sals to drill new wells, significantly deepen exisugged wells, or to drill horizontal laterals. Use <i>i</i>		7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES
1. TYPE OF WELL Gas Well			8. WELL NAME and NUMBER: NBU 922-32F3T
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONS	HORE, L.P.		9. API NUMBER: 43047503490000
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th S	PHONE N treet, Suite 600, Denver, CO, 80217 3779	NUMBER: 720 929-6515 Ext	9. FIELD and POOL or WILDCAT: NATURAL BUTTES
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2111 FNL 1824 FWL			COUNTY: UINTAH
QTR/QTR, SECTION, TOWNSHI Qtr/Qtr: SENW Section: 32	IP, RANGE, MERIDIAN: Township: 09.0S Range: 22.0E Meridian: S		STATE: UTAH
11. CHE	CK APPROPRIATE BOXES TO INDICATE N	NATURE OF NOTICE, REPORT,	OR OTHER DATA
TYPE OF SUBMISSION		TYPE OF ACTION	
The operator request on the subject we	ACIDIZE	casing repair operations ed procedures for the ell location.	Approved by the Utah Division of Oil, Gas and Mining
NAME (PLEASE PRINT)	PHONE NUMBER	TITLE	
Gina Becker SIGNATURE	720 929-6086	Regulatory Analyst II DATE	
N/A		4/7/2011	

WORKORDER #: 88122148 3/4/11

Name: <u>NBU 922-32F3T – 922-32F PAD</u>

Surface Location: SENW SEC.32, T9S, R22E

Uintah County, UT

API: 4304750349 **LEASE#:** ML-22649

ELEVATIONS: 5003' GL 5029' KB

TOTAL DEPTH: 9282' **PBTD:** 9235'

SURFACE CASING: 9 5/8", 36# J-55 @ 2341'

PRODUCTION CASING: 4 1/2", 11.6#, I-80 @ 9272'

TOC @ Surface per CBL

PERFORATIONS: Wasatch 7066' – 7104'

Mesaverde 7170' - 9116'

Tubular/Borehole	Drift	Collapse	Burst	Capacities	5		
	inches	psi	psi	Gal./ft.	Cuft/ft.		Bbl./ft.
2.375" 4.7# J-55 tbg.	1.901	8100	7700	0.1624		0.02173	0.00387
4.5" 11.6# I-80	3.875	6350	7780	0.6528		0.0872	0.01554
9.625" 36# J-55	8.921	2020	3520	3.247		0.434	0.0773
Annular Capacities							
2.375" tbg. X 4 ½" 11.6#	csg	0.4227	0.0565		0.01006		

GEOLOGICAL MARKERS, TOPS:

1304' Green River

1978' Mahogany

4557' Wasatch

7147' Mesaverde

NBU 922-32F3T - WELLHEAD REPLACEMENT PROCEDURE

PREP-WORK PRIOR TO MIRU:

- 1. Dig out down to the 2" surface casing valve or to the valve on the riser off the surface casing.
- 2. Install a tee with 2 valves, with a pressure gauge and sensor on one valve.
- 3. Open casing valve and record pressures.
- 4. Install nipple and steel hose on the other valve, the relief valve,. Do not use hammer unions. No impact equipment or tools to be used for any of this installation. Extend hose and hard piping to a downwind location at least 100' from the wellhead. Consider installing a manifold so that vent area could be in two locations approx. 90 degrees apart from the wellhead.
- 5. Open the relief valve and blow well down to the atmosphere.
- 6. Make a determination of amount of gas flow, either by installation of a choke nipple, bucket test or other.
- 7. Shut well in. Observe for rate of build-up by utilizing sensor data. Do not build-up for more than 24 hours. Vent gas through the vent line and leave open to the atmosphere.

WORKOVER PROCEDURE:

- 1. MIRU workover rig.
- 2. Kill well with 10# brine / KCL (dictated by well pressure).
- 3. Remove tree, install double BOP with blind and 2 3/8" pipe rams, with accumulator closing unit and manual back-ups. Function test BOP system.
- 4. POOH w/ tubing laying down extra tubing.
- 5. Rig up wireline service. RIH and set CBP @ ~7016'. Dump bail 4 sx cement on top of plug. POOH and RD wireline service. TIH w/ tubing and seating nipple. Land tubing ±60' above cement. RDMO.
- 6. Monitor well pressures. If surface casing is dead. MIRU. ND WH and NU BOP. POOH w/ tubing.
- 7. Depending on conditions at wellsite, continue with either CUT/PATCH Procedure or BACK-OFF Procedure.

CUT/PATCH PROCEDURE:

- 1. PU internal casing cutters and RIH. Cut casing at +/- 30' from surface.
- 2. POOH, LD cutters and casing.
- 3. PU 7 3/8" overshot with 4 ½" right hand standard wicker grapple, 1 4 ¾" drill collar with 3 ½" IF threads, pup joint, manual bumper sub, and crossovers. If casing cut is deeper than ±30' utilize >7000 ft-lb torque pipe as needed. Pull a minimum of 10,000# to keep grapple engaged if cement top is high (<~900'). If cement top is low (>~900'), more weight will be required to put casing in neutral. Torque casing string to ±7000 ft-lbs, count number of turns to make-up, and document in the daily report. Ensure that tongs are safely anchored to rig and that all personnel are at a safe working distance from the tongs during torque-up and torque release. After initial make-up, place pipe torque to neutral and mark pipe. Place ±7000 ft-lbs on casing a second time, count turns, then return pipe torque to neutral and count turns. Repeat if torque-up turns do not equal torque release turns. Once torque-in equals torque-out, release overshot, POOH, and lay down.
- 4. TIH w/ skirted mill and dress off the fish top for approximately ½ hour. TOOH.
- 5. PU & RIH w/ $4\frac{1}{2}$ " 10k external casing patch on $4\frac{1}{2}$ " P-110 casing. Ensure that sliding sleeve assembly shifts ±3' and casing tags no-go portion of patch. NOTE: Shear pins will shear at 3500 to 4500 lbs.
- 6. Latch fish, PU to 100,000# tension. RU B&C. Cycle pressure test to 7,000# / 9,000# psi.
- 7. Install slips. Land casing w/ 80,000# tension.
- 8. Cut-off and dress 4 ½" casing stub.
- 9. NUWH. PU 3 7/8" bit, POBS and RIH. D/O cement and plug ~6966'. Clean out to PBTD (9235').
- 10. POOH, land tbg and pump off POBS.
- 11. NUWH, RDMO. Turn well over to production ops.

BACK-OFF PROCEDURE:

- 1. PU internal casing cutters and RIH. Cut casing at +/- 6' from surface.
- 2. POOH, LD cutters and casing.
- 3. PU 4 ½" overshot. RIH, latch fish. Pick string weight to neutral.
- 4. MIRU casing crew and wireline services. RIH and shoot string shot at casing collar @ ± 46'.
- 5. Back-off casing, POOH.

- 6. PU new casing joint with buttress threads and entry guide and RIH. Tag casing top. Thread into casing and torque up to ±7000 ft-lbs, count number of additional turns to make-up, and document in the daily report. Ensure that tongs are safely anchored to rig and that all personnel are at a safe working distance from the tongs during torque-up and torque release. After initial make-up, place pipe torque to neutral and mark pipe. Place ±7000 ft-lbs on casing a second time, count turns, then return pipe torque to neutral and count turns. Repeat if torque-up turns do not equal torque release turns. Once torque-in equals torque-out go to step 7.
- 7. PU 100,000# tension string weight. RU B&C. Cycle pressure test to 7,000# / 9,000# psi.
- 8. Install slips. Land casing w/ 80,000# tension.
- 9. Cut-off and dress 4 ½" casing stub.
- 10. NUWH. PU 3 7/8" bit, POBS and RIH. D/O cement and plug ~6966'. Clean out to PBTD (9235').
- 11. POOH, land tbg and pump off POBS.
- 12. NUWH, RDMO. Turn well over to production ops.




Logan High Pressure Casing Patches Assembly Procedure

All parts should be thoroughly greased before being assembled.

- 1. Install all four Logan Type "L" Packers in the spaces provided in the Casing Patch Bowl. Refer to diagram provided for proper installation.
- 2. Install Packer Protector from the Basket Grapple end of the Bowl. The beveled end of the Packer Protector goes in first. Carefully push the Packer Protector through the four Type "L" Packers.
- 3. Align Shear Pin Holes in Packer Protector so that the holes have just passed into the counter bore at the Top Sub end, refer to diagram. The Packer Protector is provided with four Shear Pin Holes. Use only two holes, 180 degrees apart and install the pins.
- 4. Screw the Basket Grapple in from the lower end of the Bowl, using left-hand rotation. The Tang Slot in the Basket Grapple must land in line with the slot in the Bowl.
- 5. Insert the Basket Grapple Control into the end of the Bowl. Align Tang on the Basket Grapple Control with the Tang Slot of the Bowl and Basket Grapple. This secures the Bowl and the Basket Grapple together.
- 6. Install the Cutlipped Guide into the lower end of the Bowl.
- 7. Install O-Rings on the two five-foot long Extensions. Screw the first Extension into the top end of the Bowl. Screw the second Extension into the top end of the first Extension.
- 8. Install O-Ring on Top Sub. Screw Top Sub into top end of second Extension.

Follow recommended Make-Up Torque as provided in chart.



RECEIVED Apr. 07, 2011

STRENGTH DATA FOR LOGAN 5.88" OD "L" TYPE CSG PATCH 4-1/2 CASING, 10K PSI MAX WP 125K YIELD MAT'L LOGAN ASSEMBLY NO. 510L-005 -000



COLLAPSE PRESSURE: 11,222 PSI @ 0 TENSILE 8,634 PSI @ 220K TENSILE

Tensile Strength @ Yield: Tensile Strength w/ 0 Int. Press.= 472,791lbs. Tensile Strength w/ 10K Int. Press.= 313,748lbs.

DATA BY SLS 11/16/2009

	STATE OF UTAH		FORM 9
	5.LEASE DESIGNATION AND SERIAL NUMBER: ML 22649		
SUNDF	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:		
	sals to drill new wells, significantly deepen igged wells, or to drill horizontal laterals. U		7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES
1. TYPE OF WELL Gas Well			8. WELL NAME and NUMBER: NBU 922-32F3T
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONS	HORE, L.P.		9. API NUMBER: 43047503490000
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th S	PHOI treet, Suite 600, Denver, CO, 80217 3779	NE NUMBER: 720 929-6515 Ext	9. FIELD and POOL or WILDCAT: NATURAL BUTTES
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2111 FNL 1824 FWL			COUNTY: UINTAH
QTR/QTR, SECTION, TOWNSHI Qtr/Qtr: SENW Section: 32	(P, RANGE, MERIDIAN: Township: 09.0S Range: 22.0E Meridian: S	5	STATE: UTAH
11. CHE	CK APPROPRIATE BOXES TO INDICAT	E NATURE OF NOTICE, REPORT,	OR OTHER DATA
TYPE OF SUBMISSION		TYPE OF ACTION	
	ACIDIZE	☐ ALTER CASING	✓ CASING REPAIR
☐ NOTICE OF INTENT	☐ CHANGE TO PREVIOUS PLANS	☐ CHANGE TUBING	CHANGE WELL NAME
Approximate date work will start:	☐ CHANGE WELL STATUS	☐ COMMINGLE PRODUCING FORMATIONS	CONVERT WELL TYPE
✓ SUBSEQUENT REPORT	DEEPEN	FRACTURE TREAT	NEW CONSTRUCTION
Date of Work Completion: 5/26/2011	OPERATOR CHANGE	☐ PLUG AND ABANDON	□ PLUG BACK
	PRODUCTION START OR RESUME	RECLAMATION OF WELL SITE	RECOMPLETE DIFFERENT FORMATION
SPUD REPORT Date of Spud:	REPERFORATE CURRENT FORMATION	SIDETRACK TO REPAIR WELL	TEMPORARY ABANDON
	TUBING REPAIR	□ VENT OR FLARE	WATER DISPOSAL
DRILLING REPORT	☐ WATER SHUTOFF	SI TA STATUS EXTENSION	APD EXTENSION
Report Date:			
	☐ WILDCAT WELL DETERMINATION	✓ OTHER	OTHER: Wellhead Repair
	MPLETED OPERATIONS. Clearly show all pert		olumes, etc.
	AS CONCLUDED WELLHEAD/CATION. PLEASE SEE THE ATTA		
	ORY FOR DETAILS OF THE OP		Accepted by the
			Jtah Division of
		Oil	l, Gas and Mining
		FOR	R RECORD ONLY
NAME (PLEASE PRINT) Gina Becker	PHONE NUMBER 720 929-6086	TITLE Regulatory Analyst II	
SIGNATURE N/A		DATE 5/26/2011	

				US	ROC	KIES R	EGION	
			0	perat	ion S	umma	ary Repor	t
Vell: NBU 922	-32F3T [BLUE]		Spud Co	nductor	: 6/17/20	009	Spud Date: 6/	21/2009
Project: UTAH-	-UINTAH		Site: NB	U 922-32	2F PAD			Rig Name No: MILES-GRAY 1/1
vent: WELL V	VORK EXPENSE		Start Da	te: 5/5/20	011			End Date: 5/20/2011
Active Datum:	RKB @5,029.00ft	(above Mear	n Sea Leve	UWI: 0	/9/S/22/E	=/32/0/S\	WSENW/26/PM	/N/2,111.00/W/0/1,824.00/0/0
Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
5/18/2011	7:00 - 7:15	0.25	WO/REP	48		Р		JSA/SAFTY MEETING
	7:15 - 8:30	1.25	WO/REP	30	Α	Р		MIRU, KILL WELL 40BBLS TUB, 60BBLS CSG ND/WH, NU/BOP
	8:30 - 11:00	2.50	WO/REP	31	I	Р		TOOH 2 3/8" TUB, 269 JTS L-80 TBG, LAY DN 3 BAD JTS,
	11:00 - 15:00	4.00	WO/REP	34	I	Р		R/U CUTTER WIRELINE, RIH W/ GAUGE RING TO 7000', RIH W/ BAKER 8K CBP, SET CBP @ 6930', DUMP BAIL 4 SACKS CEMENT ON TOP OF CBP, PRESSURE TEST CBP TO 500#, OK, SHUT WELL IN R/D WIRELINE, PREPARE TO REPAIR WELL HEAD IN AM, SDFN
5/19/2011	7:00 - 7:15	0.25	WO/REP	48		Р		JSA/SAFTY MEETING
	7:15 - 10:00	2.75	WO/REP	34				PRESSURE ON WELL, R/U CUTTER WIRELINE, RIH W/BAKER 8K CBP SET @ 6835', R/D WIRELINE

	Sunary	Number	: 153	19 AP	ı we.	II Number:	43047503490000		
	US ROCKIES REGION								
Operation Summary Report									
Well: NBU 922-32F3T [BLUE] Spud Conductor: 6/17/2009 Spud Date: 6/21/2009									
Project: UTAH-UINTAH		Site: NB	U 922-3	2F PAD			Rig Name No: MILES-GRAY 1/1		
Event: WELL WORK EXF	PENSE	Start Dat	te: 5/5/2	011			End Date: 5/20/2011		
Active Datum: RKB @5,0	29.00ft (above Mea	an Sea Leve	UWI: 0	/9/S/22/E	/32/0/S	WSENW/26/PM/	N/2,111.00/W/0/1,824.00/0/0		
Date Tin Start-		Phase	Code	Sub Code	P/U	MD From (ft)	Operation		
10:00 -		WO/REP	30		Р		NO PRESSURE ON WELL, N/D BOPS AND CSG BOWL, P/U INSIDE CUTTER AND POWER SWIVEL, RIH CUT 4 1/2" CSG OFF 1' BELOW HANGER, LAY DOWN CUTTER AND SWIVEL, P/O HANGER AND CSG STUB, TOP OF CEMENT 36' BELOW SURFACE, P/U OVERSHOT LATCH ONTO CSG, R/U WIRELINE RIH W/STRING SHOT, R/U CSG TONGS BACK OFF AT SUB, P/O LAY DOWN OVERSHOT AND CSG SUB, P/U NEW SUB WITH SKIRTED PIN, RIH SCREWED INTO CSG W/TORQUE TO 7000# NO EXTRA TURNS, R/D TONGS		
13:00 -	14:00 1.00	WO/REP	33	С	Р		R/U B&C QUICK TEST, PRESSURE TEST CSG W/LOW TEST 1000# FOR 15 MINS OK, HIGH TEST 3500# FOR 30 MIN OK, R/D TESTER		
14:00 -	15:00 1.00	WO/REP	30		Р		PUT SLIPS IN CSG BOWL, LAND 4 1/2" CSG W/80,000# TENSION, N/U CSG BOWL AND TUBING SPOOL, TEST BOWL OK, N/U BOPS AND TBG EQUIP.		
15:00 -	18:00 3.00	WO/REP	31	1	Р		P/U 3 7/8" BIT AND POBS, TIH WITH 2 3/8" TBG, BROACH TBG IN HOLE, TAG CEMENT @6835, PREPARE TO DRILL OUT IN THE AM, SHUT WELL IN		
5/20/2011 7:00 -		WO/REP	48		Р		JSA/SAFTY MEETING		
7:15 -	16:00 8.75	WO/REP	44		Р		TEST BOPS TO 3000# OK, ESTB CIRC W/N2/FOAM UNIT, DRILL OUT CBP'S AND CEMENT FROM 6835 TO 6930', CIRC CLEAN, RIN TAG @ 9082', DRILLED OUT TO 9209', P/O LAY DN 21 JOINTS ON TRAILER, RD PWR SWIVEL AND FOAM UNIT, LANDED TBG W/ TBG HANGER W/ 269 JOINTS OF L80 TBG, EOT 8555.02, ND BOPS AND TBG EQUIP, NU WH, PUMP BIT OFF @ 700#, SHUT WELL IN 700# ON CSG, SITP= ZERO#		
							KB 26.00 HANGER .83 269 JTS 2 3/8" L80 TUBING 8525.99 XN- NIPPLE 2.20		

EOT

8555.02